



OFFICE OF THE PANCHAYAT SAMITI, BASUDEVPUR

At/Po: Basudevpur, Dist: Bhadrak Email: ori-basudevpur@nic.in

INVITATION FOR BIDS (IFB)

BID IDENTIFICATION ON 01/2021-22, Date:- 02/08/2021

Block Development officer, Basudevpur on behalf of Panchayat Samiti, Basudevpur invites percentage Rate bids in single sealed cover system for the construction of work as detailed in the table below, from the eligible contractor of Govt, of odisha equivalents grade/class registered with central Govt/MES/Railways for execution of civil works. The proof of registration from the appropriate authority along with ITCC and system generated GST Registration and copy of PAN shall be enclosed along with the bid. The bidders may submit bids for any or all the following works in the office of the Panchyat samiti, Basudevpur. One bidder can submit one bid only for a particular work. The cover containing the bid should be super scribed as tender for the work "name of the work as the case may be"

1. Bid document consisting of specification, the schedule of quantities and the set of terms & conditions of contractor and other necessary Documents can be seen in the web site www.bhadrak.nic.in or purchased from this office on payment of specified amount (non-refundable) during office hours. The bidders who will done load the documents online must have to obtain the money receipt towards cost of document from this office before the schedule time.
2. Bids must be accompanied with bid security and receipt against cost of bid documents of the amount as specified for the work in the table along bid documents cost of bid documents shall be in shape of demand draft issued from any Nationalized Schedule Bank located in the state of Odisha in favour of Block Development officer Basudevpur, Bid security will have to be valid for 45 days beyond the validity of the bid. Bids shall be received in the office of Panchayat Samiti Basudevpur up to 3.00PM of date 16/08/2021 Expect Govt holidays. Same will be dropped in tender box available at Block Office Basudevpur or by registered post/speed post, no other courier service shall be accepted. The authority will not responsible for any postal delay. Further any registered tender of it is received after scheduled date & time will not taken to be consideration.

3. Bids received shall be opened at 3.30 PM on date 16/08/2021 in the office of the Panchayat Samiti Basudevpur in the presence of the bidders or their authorized representatives who were to attend thereof. In case the office happens to be closed on the stipulated date of opening of bids as specified, the bids will be opened on the next working day at the same time and venue.
4. All the tenders where rate quoted is more than 15% less the scheduled rate will be rejected.
5. ST/SC tendered can avail facilities as per Govt. circular.
6. The bidders shall have to furnish an affidavit along with the bid regarding at the authenticity of bid document.
7. As GST has come in to force with effect from 01/07/2017 so the guideline with date of tax & other term & condition will be made applicable to this tender as per law from time to time.
8. Other details can be seen in the bidding document.
9. The authority reserves right to reject / cancel the bids without assigning any reason thereof.
10. Proposed publication/advertisement on date:- 05/08/2021
11. Date of purchase of bids & deposit of bids- 06/08/21 to 14/08/2021
12. Date of opening of tender bid- 16/08/2021 at 3.30PM

SI No	Name of the work	Amount put to tender (In Lacks)	EMD	Time for completion	Class of contractor	Cost of document
1	Construction of OPD Building at PHC(N) Naikanidihi of Naikanidihi GP	44,42,353.00	No EMD is required But Bid security declaration should be furnished by the Bidders as mentioned in the DTCN	Nine Calendar months	A&B	6000.00


 Block Development officer
 Basudevpur

**TENDER SCHEDULE (B.O.Q.) FOR " CONSTRUCTION OF OPD BUILDING " AT -NAIKANIDIHI OF
BASUDEVPUR BLOCK - (UNDER BHADRAK DISTRICT.**

TENDER SCHEDULE

S.Ino	Items	Unit	Quantity	Rate in Rs/P	Amount in Rs/P
1	300 mm dia Double under reamed pile 5.00 mtr depth with R.C.C. M-20 excluding cost of steel & labour charges for cutting, bending & binding of steel, As per direction of Engineer in charge	Each	64	₹ 5,005.54	₹ 3,20,354.00
2	Earthwork excavation in hard soil with in 50 mtr initial lead & 1.5 mtr lift including bed dressing, levelling etc complete as per the direction of Engineer in charge.	1cum	86.60	₹ 184.59	₹ 15,986.00
3	Earthwork excavation in hard soil with in 50 mtr initial lead & 1.5 mtr lift including bed dressing, levelling etc complete as per the direction of Engineer in charge. (One extra lift)	1cum	21.0764	₹ 199.12	₹ 4,197.00
4	Fine dressing to approach road as per direction of Engineer in charge	1sqm	119.00	₹ 3.58	₹ 426.00
5	Filling (F&P) with sand well water rammed etc complete as per direction of Engineer in charge.	1cum	171.4925	₹ 965.38	₹ 1,65,556.00
6	P.C.C. (1:3:6) using 40 mm size h.g. Metal including cost of materials, conveyance, royalty all labour etc complete as per the direction of engineer in charge.	1cum	44.1185	₹ 4,892.77	₹ 2,15,862.00
7	R.C.C. M20- grade using 20mm & down graded h.g. C.b. Chips as per direction of Engineer in charge.				
(a)	Pile cap Grade beam	1cum	28.4611	₹ 5,590.05	₹ 1,59,099.00
(b)	Column & beam (G.F.)	1cum	19.0696	₹ 10,901.42	₹ 2,07,886.00
(c)	Column & beam (1st.F.)	1cum	0.6239	₹ 12,148.78	₹ 7,579.00
(f)	Lintel (G.F.)	1cum	5.8036	₹ 8,787.63	₹ 51,000.00
(i)	Slab & chhaja (G.F.)	1cum	49.9830	₹ 9,372.26	₹ 4,68,453.00
(m)	Stair case (G.F.)	1cum	1.7879	₹ 10,415.91	₹ 18,622.00
8	Cost of steel including all & carriage including labour for cutting, bending & binding including cost of binding wire etc. as per direction of Engineer in charge (G.F.)	1Qntl	139.06	₹ 7,484.36	₹ 10,40,808.00
9	Cost of steel including all & carriage including labour for cutting, bending & binding including cost of binding wire etc. as per direction of Engineer in charge (1st.F.)	1Qntl	0.555	₹ 7,507.54	₹ 4,169.00

Depend
16.1.24

10	Fly ash Brick masonry in C.M. (1:6) for (F&P) including cost, conveyance, labour all complete in (F&P) quantity including septictankas per direction of Engineer in charge.	1 cum	41.045	₹ 4,539.52	₹ 1,86,325.00
11	Fly ash Brick masonry in C.M. (1:6) for Super Structure including cost, conveyance, labour all complete in as per direction of Engineer in charge.	1 cum	87.30	₹ 4,572.52	₹ 3,99,181.00
12	Fly ash Brick masonry in C.M. (1:6) for 1st floor including cost, conveyance, labour all complete in as per direction of Engineer in charge. (1st floor)	1 cum	15.514	₹ 4,832.10	₹ 74,966.00
13	6 mm thick cp in (1:4) cm over R.C.C. Surface including slurry treatment etc complete as per the direction of Engineer in charge. (Ground floor)	1 sqm	166.78	155.09	₹ 25,866.00
14	12 mm thick cp in (1:6) cm over brick work outside only including cost of materials, labour all complete as per the direction of Engineer in charge. (G.F.)	1 sqm	150.43	143.30	₹ 21,557.00
15	12 mm thick cp in (1:6) cm over brick work outside only including cost of materials, labour all complete as per the direction of Engineer in charge. (1st.F.)	1 sqm	102.80	146.53	₹ 15,064.00
16	16 mm thick cp in (1:6) cm over brick work in side side only including cost of materials, labour all complete as per the direction of Engineer in charge. (G.F.)	1 sqm	708.12	202.63	₹ 1,43,486.00
17	16 mm thick cp in (1:6) cm over brick work in side side only including cost of materials, labour all complete as per the direction of Engineer in charge. (1st.F.)	1 sqm	86.91	207.42	₹ 18,028.00
18	20 mm thick cp in (1:4) cm over roof grading only including cost of materials, labour all complete as per the direction of Engineer in charge. (2nd floor)	1 sqm	380.20	224.49	₹ 85,350.00
19	12 mm thick cp in (1:4) cm with cement punning & bitumen painting over brick work (plinth & Septic tank) only including cost of materials, labour all complete as per the direction of Engineer in charge.	1 sqm	92.92	161.72	₹ 15,027.00
20	2.5 cm thick D.P.C. In plinth including cost of materials labour all complete as the direction of Engineer in charge	1 sqm	34.70	287.66	₹ 9,982.00
21	Providing vetrified floor tile of size 600 mm x600mm in (1:1) cm of approved quality as per the direction of engineer in charge. (Ground floor)	1 sqm	166.70	898.45	₹ 1,49,775.00

Accepted
16.8.21
AB

22	Providing floor tile of size 300 mm x300mm for floor area of toilets of approved quality as per the direction of engineer in charge.(Ground floor)	1sqm	7.80	993.77	₹	7,751.00
23	Providing Glazed tile of size 300 mm x300mm for wall area of toilets of approved quality as per the direction of engineer in charge.(Ground floor)	1sqm	308.86	740.53	₹	2,28,721.00
24	Two coat cement wash over plaster surface including cost of materials labour etc complete as per the direction of Engineer in charge.(G.F.)	1sqm	1055.02	14.11	₹	14,891.00
25	Two coat cement wash over plaster surface including cost of materials labour etc complete as per the direction of Engineer in charge.(1st .F.)	1sqm	189.72	14.49	₹	2,750.00
26	Providing water cement primer on the plaster surface with cost ,conveyance & labour all complete as per direction of Engineer in charge.	1sqm	1055.02	55.92	₹	58,995.00
27	Providing coat weather coat over plaster surface (out side wall) including cost of materials labour all complete as per the direction of Engineer in charge.(G.F.)	1sqm	196.47	73.57	₹	14,455.00
28	Providing ^{two} coat weather coat over plaster surface (out side wall) including cost of materials labour all complete as per the direction of Engineer in charge.(1st .F.)	1sqm	189.72	76.15	₹	14,447.00
29	Providing Two coat, Plstic emolusionpaint over plaster surface (in side wall) including cost of materials labour all complete as per the direction of Engineer in charge.(Ground floor)	1sqm	858.55	80.09	₹	68,759.00
30	Providing water based putty all complete as per direction of Engineer in Charge	1sqm	858.55	71.38	₹	61,284.00
31	Painting two coats with enamel paint with prme coat including cost of materials all labour etc complete as per the direction of Engineer in charge.(Ground floor)	1sqm	121.77	190.08	₹	23,146.00
32	C.C. (1:2:4) using 12 mm thick h.g.c.b. chips all complete as per direction of Engineer in charge .	1cum	11.90	6184.40	₹	73,594.00
33	Hire & running charges of vibrater 2.5cum /hour as per direction of Engineer in chrage.	1 hour	14.11	92.17	₹	1,301.00
34	Rigid & Smooth centering for casting of mass concrete. as per direction of Engineer in chrage.	1sqm	27.20	103.13	₹	2,805.00
35	Filling (F&P) with excavated earth all complete as per direction of engineer in charge.	1cum	11.48	102.55	₹	1,177.00

Suppl
11.3.21

36	Providing for stainless steel stair case hand railings with 3 nos horizontal bar with vertical circular pipe including cost of materials labour all complete as per direction of Engineer in charge. (Ground floor)	1mtr	7.3171	3497.54	₹	25,592.00
37	Labour charges for fitting fixing of GCI Sheet roofing including cost of GCI Sheet as per direction Engineer In charge.	1sqm	19.51	479.1577	₹	9,348.00
38	Non sal wood work for fitting fixing of burgha, rafters, ridges all complete as per direction of Engineer in charge.	1cum	0.1462	34092.36	₹	4,983.00
39	Dry brick Khoa filling inside soak pit with cost, conveyance & labour all complete as per the direction of Engineer in charge.	1cum	3.1696	1183.12	₹	3,750.00

Total 39 items.

(Rupees Forty four lakh forty two thousand three hundred fifty three) only.

₹ 44,42,353.00

Tender value (Excluding G.S.T. 12%)

Rate to be quoted % basis

[Signature]
16.3.21
J.E.

[Signature]
16.03.2021
A.E.E.

[Signature]
B.D.O.
S.D.A. Development Officer
Bansudapur

[Signature]
31.03.21
Addl. Project Director (Tech.)
D.R..D.A. Bhadrak

[Signature]
27.04.21
Junior Engineer
Estimator (Tech. Cell) P.R. & D.W. Deptt
Govt. of Odisha, Bhubaneswar

Approved the Tender schedule
for 39 (Thirty nine) items amounting
to Rs. 44,42,353/- only.

[Signature]
28.4.21
Superintending Engineer
Panchayati Raj & Drinking Water Deptt
Govt. of Odisha, Bhubaneswar