


QUOTATION DETAILS

**NAME OF WORK : Establishment of NBSU at CHC Agarpada, Bhadrak for the FY 2022-23
(Electrification)**

Sl No	Description	Qty	Unit	Rate	Amount	Quoted Rate in Rs	Quoted Amount in Rs
1	Supplying fittings and fixing of 5-star 1.5 ton carrier/Hitachi/Voltas split ac including all in complete.	1	No	36990.00	36990.00		
2	S/F to Automatic voltage stabilizer make shakti/V guard/Alpha	1	No	8500.00	8500.00		
3	S/F to Sfe Guard to outdoor Unit	1	No	4200.00	4200.00		
4	S/F of nylon PVC Pipe for drainage of Water	1	No	127.00	127.00		
5	Installational charge of AC Machine	1	No	1500.00	1500.00		
6	S/F to AC Point consisting of 32Amp industrial male female socket & top with 32 AMP crabtree starter with all connection	1	No	1515.00	1515.00		
7	Recessed wiring to light point / Exhaust Fan Point with 1.5 sq mm FR PVC insulated ,single core multistrand copper conductor of ISI mark in 20 mm dia non-metalic PVC flexible conduit with 5 Amp , 250 V, ISI marked piano type switch and ISI Marked ceiling rose mounted on MS box having front bakelite cover of suitable size, with 1.0 sq mm FR PVC insulated single core multistrand copper conductor and earth wire including all accessories and connection as per direction of engineer in charge (Make of wire = Finollex / L & T / Anchor / Havels / V-Guard) (deducting the						
(a)	-do-.....Group A (1.2.1-1.24.2)	2	Point	308.05	616.10		
(b)	-do- Group B (1.2.2-1.24.2)	3	Point	474.70	1424.10		
8	SIF of 16/18 SWG metal box of following sizes (Nominal size) in recess with suitable size of phenolic laminated sheet cover in front including cutting the wall and making good the same in case of recessed conduit as required.						
f	-do-200mmx150mmx60mm deep(1.24.7)	4	No	151.50	606.00		
9	S/F of 5 amp swith and 5A.socket out let of ISI marked on existing board (1.25.1 & 1.25.4)	1	No	89.32	89.32		
10	S/F of 15 amp swith and 15A.socket out let of ISI marked on existing board (1.25.1 & 1.25.4)	1	No	278.00	278.00		
11	Earthing with G.I. earth pipe 3 mtr. Long 40mm dia ISI marked including accessories and providing masonry enclosure with cover plate,C.I	1	set	2359.36	2359.36		
				Total Rs	58204.88		
				GST 18%	10477.00		
				Total Rs	68682.00		




CDM & PHO, Bhadrak