

OFFICE OF THE PANCHAYAT SAMITI, BONTH

At/PO- Bonth, Dist- Bhadrak, PIN- 756114

E-mail id- ori-bonth@nic.in

Letter no.....642.....

Date.. 20.03.2023

DETAIL TENDER CALL NOTICE 01/BDO,BONTH OF 2022-23

The Block Development Officer, Bonth invites a sealed percentage rate tender in single cover system on behalf of Governor of Odisha from registered & eligible class of Civil contractor of the state P W D (R&B) / Water resource / Rural Works / M.I/C.P.W.D for the following works. **The Block Development Officer, Bonth reserves the right to reject any or all the tenders without assigning any reason thereof.** Other details can be seen in **Annexure-1**.

Term & Condition

- 1. Cost of Tender Paper :-** The Tender Specification can be obtained from www.bhadrak.nic.in & payment towards the cost of Tender papers as mentioned (Non-Refundable) in shape of Demand Draft /Term Deposit to be drawn in favour of Block Development Officer, Bonth in any Nationalized Bank having its branch at Bhadrak on any working day **on or of from 04.04.2023 to 17.04.2023** for the above work.
- 2. Date of receipt and mode of submission of Tender Papers:-** The tender papers have to be submitted as sealed tender papers in complete shape through **Registered Post/ Speed Post** only, directly sending it to the BDO Bonth in his official postal address. The last date of receipt of tender paper is **17.04.2023 upto 5.30 P.M.** The undersigned will not be responsible for postal delay if any non-receipt of the tender papers in time. **The bidders must super scribe the name of the work/project on the sealed envelope.**
- 3. Date of Opening of Tender Paper:-**The tender paper shall be opened on **18.04.2023** at **4.00 P.M** in the presence of the bidders or in their authorized representative having **written authorization** for the purpose before the tender committee in the conference Hall of Bonth Block Office.
- 4. Documents to be attached:-**The following documents should be furnished with the tender paper failing which the tender will be liable for rejection.
(A) Self attested copy of contractor Registration Certificate.
(B) Self attested copy of PAN card/Certificate of GSTIN.

- (C) Demand Draft/Term Deposit Receipt of Paper Cost & EMD.
- (D) Self attested copy of caste certificate issued by competent authorities in case of SC/ST Contractors desirous of availing preference.
- (E) The bidders must produce an original affidavit in support of the authenticity of documents attached with the tender papers.
- (F) Joint venture consortium agreements are not allowed to participate tender.
5. Shortfall of any required documents and tender paper is liable for rejection.
6. **E.M.D @1%** of tender value shall be pledged in favour of Block Development Officer along with the bids
7. **Additional Performance Security Deposit**:- The affidavit in support of APS will be submitted by the successful bidder for the cost of less quoted in percentage of the amount put to tender before signing of the agreement of the contract.

Govt. of Odisha modification to APS will be followed as detailed below:

SI NO.	Range of Difference between the estimated cost put to tender & Bid amount	Additional performance Security to be deposited by the successful Bidder
1	Below 5%	No additional Performance Security
2	From 5% & above & below 10%	50% of (Difference between estimated cost put to tender & Bid amount)
3	From 10% & above	150% of (Difference between estimated cost put to tender & Bid amount)

8. Submission of more than one tender paper by bidder for a single work will be liable for rejection of all such tender papers.
9. **The Block Development Officer, Bonth reserves the right to reject any or all the tenders without assigning any reason thereof .Other details can be seen in the bidding documents.**
10. If rate quoted by the bidder is less than 15% of the amount put to tender, then such a bid shall be rejected & all the tenders shall be finalized basing of merits of rest bids. But if more than one bid is quoted (decimal upto two numbers will be taken for all practical purposes) either all the estimated cost put to tender or less than the estimated cost put to tender, the




tender accepting authority will finalize the tender through a transparent lottery system, where all bidders/ their authorized representative, the concerned SE/Executive Engineer of concerned Division DAO will remain present vide works Deptt O.M No- 1437 dated- 31/01/2023

11. No Tender paper shall be received through Drop Box or Courier Services & tender paper received through Drop Box or Courier Services shall be liable for rejection.

Memo No- 643

Date- 20.03.2023

Copy submitted to the Director, I & PR, Govt. of Odisha, Bhubaneswar for favour of kind information.


Block Development Officer
BONTH BLOCK
Bonth

Memo No- 644

Date- 20.03.2023

Copy Submitted to PA to Collector, Bhadrak / CDO-cum-EO, ZP, Bhadrak/ CDM & PHO, Bhadrak/ District Planning Officer /D.I & P.R.O for favour of kind information & necessary action.


20/3/2023
Block Development Officer
BONTH BLOCK
Bonth

Memo No- 645

Date- 20.03.2023

Copy to EE, Bhadrak/ EE, R.W.S & S, Bhadrak, EE R & B Divison, Bhadrak/ EE,M.I. Divison, Bhadrak/EE,R.W Divison, Bhadrak/ All BDOs of Bhadrak District/ Tahasildar, Bonth/ IIC, Bonth, Bonth PS/ CDPO, ICDS, Bonth for information & necessary action with request to display in their Notice board for wide circulation.


20/3/2023
Block Development Officer
BONTH BLOCK
Bonth

Memo No- 646

Date- 20.03.2023

Copy to NIC, Bhadrak uploading the detail tender call notice, tender schedule and the bid documents in the official website of Bhadrak i.e www.bhadrak.nic.in


20/3/2023
Block Development Officer
BONTH BLOCK
Bonth

Memo No- 647(c)

Date- 20.03.2023

Copy to Office Notice Board & C.P, Bonth Block to assist for uploading the DTCN & bid documents at NIC, Bhadrak.


20/3/2023
Block Development Officer
BONTH BLOCK
Bonth

Annexure-1

SI NO.	NAME OF THE WORK	APPROXI. EST COST TO TENDER	CLASS OF CONTRACTOR	EMD(1%)Approx	COST OF TENDER PAPER	TIME OF COMPLETION
1	Construction of sub-center building under 15th CFC health sector at Kenduapada	Rs. 30,82,045/-	'C' & 'B'	Rs.31,000/-	Rs.6,000/-	SIX CALENDAR MONTH


20/3/2023
Block Development Officer
BONTH BLOCK
Bonth

TENDER SCHEDULE (B.O.Q.) FOR " CONSTRUCTION OF BUILDING LESS SUB HEALTH CENTRE OUT OF 15th CFC HEALTH SECTOR , AT- KENDUAPADA , KENDUAPADA G.P OF BONTH BLOCK UNDER BHADRAK DISTRICT.

TENDER SCHEDULE

S.Ino	Items	Unit	Quantity	Rate in Rs/P	Amount in Rs/P
1	300 mm dia Double under reamed pile 6.00 mtr depth with R.C.C. M-20 excluding cost of steel & labour charges for cutting, bending & binding of steel, As per direction of Engineer in charge	Each	34	₹ 5,618.26	₹ 1,91,021.00
2	300 mm dia single under reamed pile 1.50mtr depth with R.C.C. M-20 excluding cost of steel & labour charges for cutting, bending & binding of steel, As per direction of Engineer in charge	Each	2	₹ 1,851.67	₹ 3,703.00
3	Earthwork excavation in hard soil within 50 mtr initial lead & 1.5 mtr lift including bed dressing , levelling etc complete as per the direction of Engineer in charge.	1cum	48.77	₹ 199.58	₹ 9,734.00
4	Earthwork excavation in hard soil within 50 mtr initial lead & 1.5 mtr lift including bed dressing , levelling etc complete as per the direction of Engineer in charge. (One extra lift)	1cum	11.8648	₹ 215.28	₹ 2,554.00
5	Filling (F&P) with sand well water rammed etc complete as per direction of Engineer in charge.	1cum	116.0572	₹ 615.17	₹ 71,395.00
6	P.C.C. (1:3:6) using 40 mm size h.g. Metal including cost of materials, conveyance , roylty all labour etc complete as per the direction of engineer in charge.	1cum	11.0628	₹ 4,840.18	₹ 53,546.00
7	R.C.C. M20- grade using 20mm & down graded h.g. C.b. Chips as per direction of Engineer in charge.				
(a)	Pile cap Grade beam	1cum	17.4258	₹ 5,486.78	₹ 95,611.00
(b)	Column & beam (G.F.)	1cum	9.6740	₹ 11,087.82	₹ 1,07,264.00
(c)	Column & beam (1st.F.)	1cum	7.1250	₹ 12,402.51	₹ 88,368.00
(d)	Column & beam (2nd.F.)	1cum	1.5828	₹ 13,975.72	₹ 22,121.00
(e)	Lintel (G.F)	1cum	3.0351	₹ 8,800.13	₹ 26,709.00
(f)	Lintel (1.F)	1cum	2.1625	₹ 9,657.28	₹ 20,884.00
(g)	Slab & chhaja (G.F.)	1cum	14.8057	₹ 9,431.91	₹ 1,39,646.00
(h)	Slab & chhaja (1.F.)	1cum	10.7265	₹ 10,415.43	₹ 1,11,721.00
(i)	Slab & chhaja (2.F.)	1cum	1.3225	₹ 11,591.22	₹ 15,330.00
(m)	Stair case (G.F.)	1cum	1.1391	₹ 10,585.21	₹ 12,057.00
(n)	Stair case (1.F.)	1cum	1.4776	₹ 11,799.38	₹ 17,435.00


(Signature)
26.12.22
A.E


(Signature)
26.12.22
AEE
Asst. Executive Engineer

(Signature)
Block Development Officer
Bonth

(Signature)
27.12.22
Add. Executive Officer (Te)
Bhadra

8	Cost of steel including all & carriage including labour for cutting, bending & binding including cost of binding wire etc. as per direction of Engineer in charge (G.F.)	1Qtl	70.02	₹ 8,445.77	₹ 5,91,363.00
9	Cost of steel including all & carriage including labour for cutting, bending & binding including cost of binding wire etc. as per direction of Engineer in charge (1st.F.)	1Qtl	19.342	₹ 8,470.61	₹ 1,63,842.00
10	Cost of steel including all & carriage including labour for cutting, bending & binding including cost of binding wire etc. as per direction of Engineer in charge (2nd.F.)	1Qtl	2.586	₹ 8,496.69	₹ 21,970.00
11	Fly ash Brick masonry in C.M. (1:6) for (F&P) including cost, conveyance, labour all complete in (F&P) quantity including septictankas per direction of Engineer in charge.	1 cum	30.131	₹ 4,566.70	₹ 1,37,601.00
12	Fly ash Brick masonry in C.M. (1:6) for Super Structure including cost, conveyance, labour all complete in as per direction of Engineer in charge.	1 cum	50.30	₹ 4,599.70	₹ 2,31,365.00
13	Fly ash Brick masonry in C.M. (1:6) for 1st floor including cost, conveyance, labour all complete in as per direction of Engineer in charge.(1st floor)	1 cum	20.631	₹ 4,878.27	₹ 1,00,642.00
14	Fly ash Brick masonry in C.M. (1:6) for 1st floor including cost, conveyance, labour all complete in as per direction of Engineer in charge.(2nd floor)	1 cum	12.624	₹ 5,198.61	₹ 65,625.00
15	6 mm thick cp in (1:4) cm over R.C.C. Surface including slurry treatment etc complete as per the direction of Engineer in charge.(Ground floor)	1 sqm	77.42	161.42	₹ 12,497.00
16	6 mm thick cp in (1:4) cm over R.C.C. Surface including slurry treatment etc complete as per the direction of Engineer in charge.(1st floor)	1 sqm	72.67	165.45	₹ 12,023.00
17	6 mm thick cp in (1:4) cm over R.C.C. Surface including slurry treatment etc complete as per the direction of Engineer in charge.(2nd floor)	1 sqm	7.15	169.61	₹ 1,213.00
18	12 mm thick cp in (1:6) cm over brick work out side only including cost of materials, labour all complete as per the direction of Engineer in charge.(G.F.)	1 sqm	110.76	145.52	₹ 16,119.00
19	12 mm thick cp in (1:6) cm over brick work out side only including cost of materials, labour all complete as per the direction of Engineer in charge.(1st.F.)	1 sqm	86.59	148.98	₹ 12,901.00


 26.12.22
 J. E.


 26.12.22
 Asst. Executive Engineer,
 Bonth Block.


 26.12.22
 Block Development Officer
 Bonth


 Addl. Executive Engineer
 Zilla Parishad, Bonth

20	12 mm thick cp in (1:6) cm over brick work out side only including cost of materials , labour all complete as per the direction of Engineer in charge.(2nd F.)	1sqm	68.36	152.54	₹	10,428.00
21	16 mm thick cp in (1:6) cm over brick work in side side only including cost of materials , labour all complete as per the direction of Engineer in charge.(G.F.)	1sqm	402.52	207.85	₹	83,664.00
22	16 mm thick cp in (1:6) cm over brick work in side side only including cost of materials , labour all complete as per the direction of Engineer in charge.(1st.F.)	1sqm	261.08	213.00	₹	55,609.00
23	16 mm thick cp in (1:6) cm over brick work in side side only including cost of materials , labour all complete as per the direction of Engineer in charge.(2nd .F.)	1sqm	56.00	218.29	₹	12,223.00
24	20 mm thick cp in (1:4) cm over roof grading only including cost of materials , labour all complete as per the direction of Engineer in charge.1st floor)	1sqm	35.21	233.78	₹	8,232.00
25	20mm thick cp in (1:4) cm over roof grading only including cost of materials , labour all complete as per the direction of Engineer in charge.(2nd floor)	1sqm	13.16	239.07	₹	3,145.00
26	12 mm thick cp in (1:4) cmwith cement punning & bitumen painting over brick work (plinth & Septic tank) only including cost of materials , labour all complete as per the direction of Engineer in charge.	1sqm	87.40	163.93	₹	14,328.00
27	2.5 cm thick D.P.C. In plith including cost of materials labour all complete as the direction of Engineer in charge	1sqm	20.90	296.82	₹	6,203.00
28	Providing vetrified floor tile of size 600 mm x600mm over 20 mm thick (1:4) cmof approved quality as per the direction of engineer in charge. (Ground floor)	1sqm	72.42	903.51	₹	65,437.00
29	Providing vetrified floor tile of size 600 mm x600mm over 20 mm thick c.p. in (1:4) cmof approved quality as per the direction of engineer in charge. (1st floor)	1sqm	40.74	913.74	₹	37,225.00
30	Providing floor tile of size 300 mm x300mm for floor area of toilets of approved quality over 25 mm thick (1:1) cm as per the direction of engineer in charge.(Ground floor)	1sqm	20.18	779.26	₹	15,723.00
31	Providing floor tile of size 300 mm x300mm for floor area of toilets of approved quality over 25 mm thick (1:1) cm as per the direction of engineer in charge.(Ground floor)	1sqm	11.17	789.50	₹	8,823.00
32	Providing Glazed tile of size 300 mm x300mm for wall area of toilets of approved quality over 12 mm thick in (1:3)cm as per the direction of engineer in charge.(Ground floor)	1sqm	68.47	754.03	₹	51,631.00

-D/Son
26.12.22
T.E

Sush
26.12.22
Asst.Executive Engineer

Block Development Officer
Bent

17/1/23

33	Providing Glazed tile of size 300 mm x300mm for wall area of toilets of approved quality over 12 mm thick (1:3) cm as per the direction of engineer in charge.(1st floor)	1sqm	37.00	769.43	₹	28,470.00
34	One coat cement wash over plaster surface including cost of materials labour etc complete as per the direction of Engineer in charge. (G.F.)	1sqm	605.17	14.66	₹	8,869.00
35	One coat cement wash over plaster surface including cost of materials labour etc complete as per the direction of Engineer in charge.(1st .F.)	1sqm	433.71	15.06	₹	6,532.00
36	One coat cement wash over plaster surface including cost of materials labour etc complete as per the direction of Engineer in charge.(2nd Floor)	1sqm	131.51	15.49	₹	2,037.00
37	Providing water cement primer on the plaster surface with cost ,conveyance & labour all complete as per direction of Engineer in charge.(Ground floor)	1sqm	605.17	59.04	₹	35,729.00
38	Providing water cement primer on the plaster surface with cost ,conveyance & labour all complete as per direction of Engineer in charge.(1st floor)	1sqm	433.71	61.40	₹	26,630.00
39	Providing coat weather coat over plaster surface (out side wall) including cost of materials labour all complete as per the direction of Engineer in charge.(G.F.)	1sqm	125.22	77.00	₹	9,642.00
40	Providing coat weather coat over plaster surface (out side wall) including cost of materials labour all complete as per the direction of Engineer in charge.(1st .F.)	1sqm	99.97	79.75	₹	7,972.00
41	Providing coat weather coat over plaster surface (out side wall) including cost of materials labour all complete as per the direction of Engineer in charge.(2nd .F.)	1sqm	68.36	82.64	₹	5,649.00
42	Providing Two coat plastiic emolusion paint over plaster surface (in side wall) including cost of materials labour all complete as per the direction of Engineer in charge.(Ground floor)	1sqm	479.94	83.51	₹	40,082.00
43	Providing Two coat of plasitc emulsion paint over plaster surface (in side wall) including cost of materials labour all complete as per the direction of Engineer in charge.(1st floor)	1sqm	333.75	86.27	₹	28,791.00
44	Providing Two coat distemper over plaster surface (in side wall) including cost of materials labour all complete as per the direction of Engineer in charge.(2nd floor)	1sqm	63.15	73.69	₹	4,654.00
45	Providing water based putty for findhing of wall inside onlyasper the direction of Engineer in charge.(Ground floor)	1sqm	479.94	74.49	₹	35,750.00

← M/1800
26/12/22
J.E

Stash
Asst. Executive Engineer
A.E. Block

Block Development Officer
Bomh

12/12

46	Providing water based putty for findhing of wall inside onlyasper the direction of Engineer in charge.(1st floor)	1sqm	333.75	76.82	₹	25,638.00
47	Painting two coats with enamel paint with prme coat incuding cost of materials all labour etc complete asper the direction of Engineer in charge.(Ground floor)	1sqm	45.46	200.54	₹	9,117.00
48	Painting two coats with enamel paint with prme coat incuding cost of materials all labour etc complete asper the direction of Engineer in charge.(1st floor)	1sqm	116.79	209.15	₹	24,426.00
49	Painting two coats with enamel paint with prme coat incuding cost of materials all labour etc complete asper the direction of Engineer in charge.(2nd floor)	1sqm	5.12	218.18	₹	1,117.00
50	Providing for stainless steel stair case hand railings eith 3nos horizontal bar with vertical cicular pipe including cost of materials labour all complete as per direction of Engineer in charge.(Ground floor)	1mtr	7.0122	3513.40	₹	24,637.00
51	Providing for stainless steel stair case hand railings eith 3nos horizontal bar with vertical cicular pipe including cost of materials labour all complete as per direction of Engineer in charge.(1st floor)	1mtr	7.0122	3526.97	₹	24,732.00
52	Dry brick Khoa filling inside soak pit with cost , conveyance & labour all complete as per the direction of Engineer in charge.	1cum	3.1696	832.82	₹	2,640.00

(Rupees Thirty lakh eighty two thousand forty five) only.

₹ 30,82,045.00

Tender value (Excluding G.S.T. 18 %)

Rate to be quoted % basis

(Signature)
J.E. 26.12.22

(Signature)
26.12.22
A.E.E.
Asst. Executive Engineer
Bonth Block

(Signature)
26/12/22
Block Development Officer
Bonth

(Signature)
17/12/22
Addl. Executive Officer (Tech.)
Zilla Parishad, Bhadrak