

**TENDER SCHEDULE (B.O.Q) FOR " Transformation of Basudevpur CHC
Under AMA Hospital**

TENDER SCHEDULE					
Sl No	Items	Unit	Quantity	Rate in Rs/P	Amount in Rs/P
1	Dismantling and removing R.C.C.column,beam slab,staircase,landing,lintel incl.stacking the useful materials for reuse &removing the debris within 50m. lead etc. complete.	cum	19.77	1,283.52	25,378.00
2	Dismantling brick or stone masonry in lime or cement mortar under 3m. height incl.stackingthe useful materials for reuse & removing the debris within 50m. Lead etc. complete.	cum	47.59	1,230.05	58,543.00
3	Dismantling and removing 2.5cm.th.grading concrete from roof slab,cleaning the surface lowering &removing the debris etc.complete.	sqm	664.24	97.65	64,863.00
4	Removing old lime or cement plaster from walls incl. raking out joints 12mm. deep and removing the debris within 50m. lead.	sqm	556.62	64.46	35,880.00
5	Dismantling and removing old tiled flooring incl. removing the base coarse and stacking the useful materials for reuse &removing the debris within 50m. lead etc. complete.	sqm	195.59	103.97	20,336.00
6	Dismantling and removing old tiled cladding from walls incl.raking out the joints 12mm.deep and stacking the useful materials for reuse & removing the debris within 50m. lead.	sqm	278.78	54.07	15,073.00
7	Dismantling and removing doors, windows & ventilators incl.removal of frame,hinges,fasteningand stacking the same for reuse and removing the debris within 50m. lead.	sqm	177.97	346.96	61,747.00
8	Labour for fitting fixing U-PVC Door & Window(ASTM D 638-14,EN-477-95) Including cost of all(As per Lt.No-16100/dt 18.05.2020 of works Deptt.)				
	Door	sqm	125.61	9,800.00	12,31,007.00
	Window	sqm	55.56	5,800.00	3,22,238.00
9	Supplying,fitting and fixing vetrified tile in floors of size 600mm x 600mm of approved make conforming to IS:13755 laid on 20mm thick cement mortar (1:4) and filling joints with white cement of approved quality incl. cost &labour of all materials etc. complete.(For new work only)(As per revised AR 2012)	sqm	161.75	921.94	1,49,127.00
10	Fixing tiles in dados,skirtings & risers of steps on 12mm.th.C.P(1:3) jointed with neat cement slurry etc.complete in all respect.(FLOOR TILES,Ceramic TILES,GRANITES &CHEQURED TILES etc. not requiring rubbing)				-
	Ceramic Floor Tile	sqm	115.59	807.99	93,396.00
	Ceramic tiles- 20cm x 30cm wall tiles	sqm	563.65	769.55	4,33,753.00
11	6mm.th. C.P.(1:4) to RCC surface finished smooth incl.closed deep chipping & slurry treatment.	sqm	269.24	163.42	44,000.00
12	4cm.th.grading concrete(1:2:4)on old roof slab using 12mm.size &down graded chips.	sqm	664.24	636.03	4,22,473.00
13	Fly ash Brick work (1:6) etc.complete.				
	For Foundation & Plinth	cum	4.81	4,531.06	21,781.00
	Superstructre	cum	94.59	4,564.39	4,31,756.00
14	Single under reamed pile foundation with RCC M20 using 12mm size black hard granite (Crusher broken) stone chips including cost of boring but excluding cost of M.S./Tor steel and labour charges for cutting, bending and binding of steel. Single under ream pile				-
	300mm dia(3mt Depth)	nos	51.00	2,783.39	1,41,953.00

	300 mm dia(4mt Depth)	nos	26.00	3,387.47	88,074.00
15	Earth work excavation of foundation in hard soil within initial lead and lift including rough dressing and levelling etc. completed.For 100cum	cum	56.11	199.58	11,199.00
16	Filling in F&P with sand etc. complete.	cum	66.79	843.33	56,327.00
17	P.C.C(1:4:8) etc complete.	cum	3.25	4,484.61	14,593.00
18	R.C.C work of M-20grade with 20mm & down graded BHGCB chips etc.complete.	cum	67.28	4,962.87	3,33,912.00
19	12mm.th. C.P.(1:6) on brick work.	sqm	392.90	149.24	58,637.00
20	16mm.th. C.P.(1:6) on brick or stone work.	sqm	615.12	212.31	1,30,595.00
21	16mm.th. C.P.(1:6) on brick or stone work incl.neat cement punning etc.complete.	sqm	25.33	228.29	5,783.00
22	Rigid &smooth centering & shuttering for R.C.C work etc. complete.				
	3.R.C.C foundation.plinth band &column footing	sqm	146.84	106.03	15,570.00
	4.R.C.C beams & columns	sqm	196.62	766.40	1,50,691.00
	RCC Wall & Fin(Drain)	sqm	118.90	656.31	78,038.00
	Drain Slab	sqm	29.72	537.04	15,961.00
	Lintel	sqm	14.29	274.54	3,923.00
	Roof Slab	sqm	97.72	447.53	43,733.00
23	Supplying,fitting & placing uncoated HYSD bar reinforcement etc.complete.	qtl	52.33	8,763.94	4,58,597.00
24	Wall painting two coats with weather coat over a coat of wall cement primer etc complete with all cost .	sqm	665.77	125.65	83,654.00
25	Painting two coats over a coat of priming over new Iron work.	sqm	34.84	200.55	6,987.00
26	C.C.(1:3:6) with using 4cm cbhg metal metal including cost of all.	cum	15.03	4,835.27	72,673.00
27	P.C.C(1:2:4) using 12mm.size BHGCB chips.	cum	12.46	6,181.04	77,027.00
28	6mm.th. C.P.(1:4) to RCC surface finished smooth incl.closed deep chipping & slurry treatment including neat cement punning.	sqm	220.73	196.01	43,265.00
29	Wall painting one coat with wall cement primer(water bound) etc complete with all cost .	sqm	244.61	48.65	11,900.00
					53,34,443.00

(Rupees Fifty Three Lakh Thirty four thousand four Hundred forty Three Only)

Tender Value(Excluding G.S.T.@ 18%)

Rate to be Quotted % basis

Deepak
5/04/23

Junior Engineer
Basudevpur Block

Anosh
5/4/23

Asst.Executive Engineer
Basudevpur Block

Ujjwal
Block Development Officer
Basudevpur Block