

OFFICE OF THE PANCHAYAT SAMITI, BASUDEVPUR

At/Po: Basudevpur, Dist: Bhadrak Email: ori-basudevpur@nic.in

Letter No: 6625/Date: 07.12.2023

Tender Call Notice-06/2023

1. Name of the Project :- "Development of Tourist Spot at Eram in Basudevpur Block under Bhadrak District
2. Total No of Project :- 01 No
3. Class of Contractor :- "A & B" Class
4. Period of Completion :- 6 Calender Months
5. Other details :- As per DTCN.

Sl No	Procurement Officer	Available Tender On-line for bidding		Last date of receipt of Bids	Date & time of opening of Bid
		From	To		
1	2	3	4	5	6
1	Block Development Officer, Basudevpur	08.12.2023	22.12.2023	22.12.2023 12.00 PM	22.12.2023 3.30 PM

6. Further details can be seen from the website portal "[https:// www.bhadrak.nic.in](https://www.bhadrak.nic.in)
7. Any other changes/Corrigendum/Addendum may be seen only in website www.bhadrak.nic.in

S.K. Sahu
7-12-23
Block Development Officer
Basudevpur

Memo No-6626 Dated- 07.12.2023

Copy forwarded to the Manager (Publication) I & PR Department, Government of Odisha, Bhubaneswar with a request to get it published in 2 (Two) No's of leading Oriya daily & 1 (One) no of Local English daily News paper at an early date for wide circulation. The Complementary copy of the news paper containing the Tender Call notice may be sent to this office for reference and record.

S.K. Sahu
7-12-23
Block Development Officer
Basudevpur

OFFICE OF THE PANCHAYAT SAMITI, BASUDEVPUR

At/Po: Basudevpur, Dist: Bhadrak Email: ori-basudevpur@nic.in

Letter No: 6627/Date: 07.12.2023

DETAIL TENDER CALL NOTICE 06/ BDO, BASUDEVPUR OF 2023-24

The Block Development Officer, Basudevpur invites sealed percentage rate tenders in single cover system on behalf of Governor of Odisha from registered and eligible class of Civil Contractor of the state P W D (R&B)/Water resource/Rural Works/M.I/C.P.W.D for the following works. **The Block Development Officer, Basudevpur reserves the right to reject the tender without assigning any reason thereof.** Other details can be seen in **Annexure-1**.

Term & Condition

8. **Cost of Tender Paper:** The Tender specification can be obtained from www.bhadrak.nic.in & payment towards the cost of Tender papers as mentioned (Non-Refundable) in shape of **Demand Draft / Term Deposit** to be drawn in favour of Block Development Officer, Basudevpur in any Nationalized Bank having its branch at Basudevpur on any working day from **08.12.2023 to 22.12.2023** for the above work.
9. **Date of receipt and mode of submission of Tenders papers:** The tender papers have to be submitted as sealed tender papers in complete shape through **Registered Post/Speed Post** only, directly sending it to the BDO Basudevpur in his official postal address.
 - a. The last date of receipt of tender paper is **22.12.2023** up to **12.00 P.M.** The undersigned will not be responsible for postal delay if any or non-receipt of the tender papers in time. **The Bidders must super scribe the name of the work /project on the sealed envelope.**
10. **Date of Opening of Tender Paper:** The tender paper shall be opened on **22.12.2023** at **3.30 P.M** in presence of the bidders or in their authorized representative having **written authorization** for the purpose before the tender committee in the chamber of Block Development Officer.
11. **Documents to be attached:** The following documents should be furnished with the tender papers failing which the tender will be liable for rejection.
 - A. Self attested copy of Contractor Registration Certificate.
 - B. Self attested copy of PAN card.
 - C. Certificate of GSTIN.
 - D. Cost of Tender Paper
 - E. Cost of EMD

(F) Self attested copy of caste certificate issued by Competent Authorities in case of SC/ST Contractors desirous of availing preference.

(G) An affidavit to avail exemption in case of Engineer Contractor desirous of availing exemption of EMD mentioning the times of facility availed by him during this financial year.

(H) The bidders must produce an original affidavit in support of the authenticity of documents attached with the tender papers.

(I) Joint venture consortium agreements are not allowed to participate tender.

J. Shortfall of any required document(s) and Tender paper is liable for rejection.

K. In case of the lottery required to be conducted among the successful bidder in accordance with the Works Deptt. Order No-10224 dated-01.09.2015 the same will be conducted at later on in this office chamber of the undersigned. The bidders are requested to keep in touch with this office and also requested to be present during the lottery as per the scheduled date, time and venue. If qualified bidder/bidders fail to attend the lottery the same will be conducted in presence of the available bidder and the result will be binding upon them. For successful bidders the required **A.P.S** to be submitted within **seven (7) days of lottery**.

L. **E.M.D @1%** of Tender value shall be pledged in favour of Block Development Officer, Basudevpur corresponding to the respective value of works and to be deposited along with the bids.

M. **Additional Performance Security Deposit:** The affidavit in support of APS will be submitted by the successful bidder for the cost of less quoted in percentage of the amount put to tender before the signing of the agreement of the contract. (vide works Department Letter No-16659/ W dated-20.09.2022 Govt. of Odisha, Works Department) As per Office Memorandum No-6559 dated-05.06.2021 of Work Deptt. Govt.of Odisha modification to APS will be followed as detailed below:

Sl No	Range of Difference between the estimated cost put to tender and Bid amount	Additional Performance Security to be deposited by the successful Bidder
1	Below 5%	No Additional Performance Security
2	From 5% and above and below 10%	50% of (Difference between estimated cost put to tender & Bid Amount)
3	From 10% and above	150% of (Difference between estimated cost put to tender & Bid Amount)

N. Submission of more than one tender paper by a bidder for a single work will be liable for rejection of all such tender papers.

O. The Block Development Officer, Basudevpur reserves the right to reject any or all the tenders without assigning any reason thereof. Other details can be seen in the bidding documents.

P. If the rate quoted by the bidder is less than 15% of the amount put to tender, then such a bid shall be rejected and the tender shall be finalized basing of merits of rest bids. But, if more than one bid is quoted (decimal up to two numbers will be taken for all practical purposes) either all the estimated cost put to tender or less than the estimated cost put to tender, the tender accepting authority will finalize the tender through a transparent lottery system, where all bidders/their authorized representatives, the concerned SE/Executive Engineer of concerned Division DAO will remain present vide Works Deptt O.M No-1437, dated-31.01.2023.

Q. No Tender paper shall be received through Drop Box or Courier Services and tender paper received through Drop Box or Courier Services shall be liable for rejection.

S.K.Sch
7/12/23
Block Development Officer
Basudevpur

Memo No-6628 Date- 07.12.2023

Copy submitted to the Director, I & PR, Govt of Odisha, Bhubaneswar for favour of kind information.

S.K.Sch
7/12/23
Block Development Officer
Basudevpur

Memo No-6629 Date- 07.12.2023

Copy submitted to PA to Collector, Bhadrak / Chief Development Officer,cum-EO,ZP, Bhadrak/ CDM&PHO, Bhadrak/District Planning officer/ D.I & P.R.O for favour of kind information and necessary action.

S.K.Sch
7/12/23
Block Development Officer
Basudevpur

Memo No-6630 Date- 07.12.2023

Copy to EE, Bhadrak/ EE, R.W.S&S Bhadrak,/ EE R&B Division, Bhadrak/ EE, M.I. Division, Bhadrak,/ EE, R.W Division,/ Bhadrak/ All BDOs of Bhadrak District/Tahasildar, Basudevpur/IIC, Basudevpur PS/IIC, Naikanidihi PS/CDPO, ICDS, Basudevpur/EO, Municipality, Basudevpur for information & necessary action with request to display in their Notice board for wide circulation.

S.K.Sch
7/12/23
Block Development Officer
Basudevpur

Memo No- 6631 Date- 07.12.2023

Copy to NIC, Bhadrak for uploading the detail tender call notice, tender schedule and the bid documents in the official website of Bhadrak i.e WWW.bhadrak.nic.in.

SLSaha
7/12/23
Block Development Officer
gmm Basudevpur

Memo No- 6632 Date- 07.12.2023

Copy to Office Notice Board and C.P, Basudevpur Block to assist for uploading the DTCN and bid documents at NIC, Bhadrak.

SLSaha
7/12/23
Block Development Officer
gmm Basudevpur

Annexure-1

SL NO	NAME OF THE WORK	APPROXI. EST COST PUT TO TENDER	CLASS OF CONTRACTOR	EMD (1%) Approx	COST OF TENDER PAPER	TIME OF COMPLETION
1	2	3	4	5	6	7
01	"Development of Tourist Spot at Eram in Basudevpur under Bhadrak District	1,43,17,900.00	'A & B'	1,43,179.00	10,000.00	SIX CALENDER MONTHS

S.K. Sah
7/223
Block Development Officer
Basudevpur

[Signature]

BQ FOR PROPOSED DEVELOPMENT OF TOURIST SPOT AT ERAM IN BHADRAK

SI No	Items	Unit	Quantity	Rate In Rs/P	Amount In Rs/P
1	Earthwork in excavation in all types of soil for site leveling, foundation, pits, trenches and other civil works upto and including 1.5metre lift and stacking the soil upto a lead of 100 metre and including dewatering, removing slush,shoring and strutting (as required), complete as per specification and as directed by the Engineer-In-Charge.	cum	1167.35	232.30	271174.73
2	Filling at all depth with available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 15cm in depth: consolidating each deposited layer by ramming and watering complete (lead upto 100m) as directed by the Engineer-In-charge.	cum	771.13	154.87	119422.02
3	Supplying of filling sand in foundation and over areas including watering,ramming, consolidating and dressing, labours, tools, taxes etc., all complete as per the specification and direction of Engineer-In-charge.	cum	275.00	1283.38	352929.78
4	Double under reamed pile foundation with RCC M25 using 12mm size black hard granite crusher broken chips including cost of boring but excluding cost of M.S./Tor steel and labour charges for cutting, bending and binding of steel.	cum	90.00	11001.40	990126.00
5	Providing and laying P.C.C. M-10 (1:4:8) grade with 40mm & down graded H.G.C.B chips & Embedded polythene sheet including hoisting, laying, compacting, curing & watering with all T&P required for the works etc. with cost, conveyance, royalty, taxes of all materials, labour etc. complete in all respect as per specifications and direction of Engineer-in-charge.	cum	140.17	5743.57	805076.21
5	Providing and laying plain cement concrete 1:3:6 (1 cement:3 sand: 6 stone aggregate 12mm nominal size) as levelling course in foundation and plinth etc. including tempering, curring ,shuttering etc.complete all depth and height.	cum	20.00	6454.73	129094.60
7	First class Fly ash Brick masonry using bricks of size 25cm. x 12 cm. x 8 cm. having crushing strength not less than 75 kg. Per. Sqr. Cm. in cement mortar of mix(1:6) with ordinary Portland slag cement(PSC) and screened & washed sand for mortar after immersing the bricks for 6 (Six) hours in water before use in Foundation & Plinth including splays cutting, circular moulding, corbelling, chamfering and similar such type of works, watering and curing etc. including cost, conveyance, loading, unloading, royalties and taxes of all materials, cost of all labour, scaffolding, sundries, T&P required for the works etc. complete in all respect as directed by the Engineer-In-Charge.	cum	58.17	5240.74	304837.68

8	Fly ash Brick masonry using bricks of size 250 mm. x 12 cm. x 8 cm. having crushing strength not less than 75 kg. Per. Sqr. Cm. in cement mortar of mix(1:6) with ordinary Portland slag cement(PSC) and screened & washed sand for mortar after immersing the bricks for 6 (Six) hours in water before use in Super structure including splays cutting, circular moulding, corbelling, chamfering and similar such type of works, watering and curing etc. including cost, conveyance, loading, unloading, royalties and taxes of all materials, cost of all labour, scaffolding, sundries, T&P required for the works etc. complete in all respect as directed by the Engineer-In-Charge.	cum	103.82	5274.07	547557.24
9	First class Fly ash Brick masonry using bricks of size 250 mm. x 12 cm. x 8 cm. having crushing strength not less than 75 kg. Per. Sqr. Cm. in cement mortar of mix(1:4) with ordinary Portland slag cement(PSC) and screened & washed sand for mortar after immersing the bricks for 6 (Six) hours in water before use in Super structure including splays cutting, circular moulding, corbelling, chamfering and similar such type of works, watering and curing etc. including cost, conveyance, loading, unloading, royalties and taxes of all materials, cost of all labour, scaffolding, sundries, T&P required for the works etc. complete in all respect as directed by the Engineer-In-Charge.	cum	10.43	5509.06	57455.73
10	Providing, lifting, hoisting and laying Reinforced cement concrete of M-25 grade as per approved designs and drawings having a minimum compressive strength (in work test) 250 Kg. / Square cm. in 15 cm. cubes at 28 days after mixing and test conducted in accordance with I.S. 516 using 12 mm. to 20 mm. size black hard crushed broken granite stone chips and screened and washed sharp sand for mortar of approved quality from approved quarry,				0.00
11	a) Footings :-	sqm	74.46	6978.49	519626.94
12	R.C.C Wall	cum	46.75	13054.38	610279.32
13	b) Column up to plinth :-	sqm	4.97	14812.28	73580.01
14	c) Plinth beam :-	sqm	11.48	7805.51	89638.49
15	Lintel				
	Ground Floor	sqm	4.17	14049.92	58553.93
E	e) Column in S.S :-				
	Ground Floor	sqm	13.37	14812.28	198066.14
F	f) Beam				
	Ground Floor	sqm	11.48	14812.28	170104.25
G	g) Slab				
	Ground Floor	sqm	7.65	13408.34	102573.81
H	h) Staircase				
	Ground Floor	sqm	3.27	14759.87	48220.48

16	Applying, straightening, cutting, bending, placing in position and binding reinforcement steel work in RCC/reinforced brick works as per drawing and specification including preparation of respective bar bending schedule and binding (Binding wire to be used as per the IS code) etc. all complete as per direction of Engineer-in-charge. Cold Twisted bars, Thermo-Mechanically-treated bars.(SAIL, TATA TISCON, JINDAL, SHYAM STEEL)	qtl	219.71	8910.80 ✓	1957819.15 ✓
17	12mm cement plaster on external RCC/brick surfaces in cement plaster 1:6 (1 cement : 6 coarse sand) including necessary scaffolding, curing etc. all complete at all floors and all heights.	sqm	443.86	165.20 ✓	73326.33 ✓
18	16mm cement plaster on internal smooth side of RCC/brick surfaces with cement mortar of mix 1:6 (1 cement : 6 fine sand) including necessary scaffolding, curing etc. all complete at all floors and all heights.	sqm	607.19	233.41 ✓	141724.09 ✓
19	6 mm cement plaster on internal smooth side of RCC/brick surfaces with cement mortar of mix 1:4 (1 cement : 4 fine sand) including necessary scaffolding, curing etc. all complete at all floors and all heights.	sqm	824.27	177.36 ✓	146188.59 ✓
20	Providing & Fixing of WPC Door Frame size 5" x 2.5" having density 725kg/m ³ , make up of virgin polymer, wheat and rice husk fiber and Calcium silicate. 100% water proof, termite proof and fire retardant made of Alstone Chaukhat. The door will be provided with all necessary fitting & fixture of approved hardware and all materials complete as per direction of the Engineer-In-Charge.	sqm	18.12	1450.00 ✓	26273.24 ✓
21	Providing & fixing WPC Door Shutter of thick 30mm having density 660kg/m ³ make up virgin polymer with wheat and rice husk fiber. 100% water proof, termite proof and fire retardant made of Alstone WPC Door. The door will be provided with all necessary fitting & fixture of approved hardware and all materials complete as per direction of the Engineer-In-Charge at all floors and all heights.	sqm	0.78	4950.00 ✓	3851.25 ✓

23	<p>Providing and fixing of factory made (NCL/VEKA or equivalent) of colour UPVC sliding window or openable (approved colour of Frame) complete with U value=1.9-1.3 W/m²/K, flame resistance, self extinguishing, lead free comprising colour UPVC multi chambered frame having in built UPVC roller track on top and UPVC sash with wall thickness of 2.3mm duly reinforced with G.I section 2.6 mm where ever required. All corners of frame and sash will be fusion welded. After placing 12.5mm laminate glass (6mm clear toughened +1.5 pvg laminate+5mm clear glass) Annealed glass in the sash, with support of hurricane bar for high wind support. uPVC glazing bead, interlock, EPDM gasket brush shall be provided including multi lock and rollers & proper drainage system shall be provided. window frame will be fixed to the wall with 100mm long and 8mm dia. Fasteners and after fixing the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealant over backer rod of required size, of approved quality complete in all respect as per approved drawing & direction of the Engineer-In-Charge.</p>	sqm	29.40	4960.97	145852.52
24	<p>Providing and laying Vitrified flooring tiles 600x600 mm (thickness to be specified by the manufacturer) 1st quality of NITCO, SOMANY, ASIAN, KAJARIA or equivalent approved make, colours & shades laid on 20 mm thick cement mortar 1:4 (Cement: 4coarse sand) including pointing the joints with white cement and matching pigments, etc. complete as per direction of Engineer-In-Charge at all floors and all heights.</p>	sqm	222.79	950.91	211851.35
25	<p>Providing and laying Vitrified kiriting tiles 600x600 mm (thickness to be specified by the manufacturer) 1st quality of NITCO, SOMANY, ASIAN, KAJARIA or equivalent approved make, colours & shades laid on 12 mm thick cement mortar 1:3 (Cement: 3coarse sand) including pointing the joints with white cement and matching pigments, etc. complete as per direction of Engineer-In-Charge at all floors and all heights.</p>	sqm	300.00	1164.31	349293.82
26	<p>Providing and fixing 20mm thick Granite stone flooring (sample of Granite stone should be approved by EIC) for stair case trade, riser and similar locations where ever required in horizontal/vertical surfaces of required size of approved shade, colour and texture, with moulding edge & Grooving etc. laid over 25mm thick bed of cement mortar 1:1 (1 cement: 1 coarse sand) with joints treated with white cement mixed with matching pigment, epoxy touch ups including rubbing, curing, moulding and polishing to give high gloss finish etc. complete as per direction of Engineer-in-charge. In all floors and all heights.</p>	sqm	70.00	2713.50	189945.00

7	Providing and laying Matte Finish Vitrified floor (thickness to be specified by the manufacturer) 1st quality conforming to IS: 15622 of NITCO, SOMANY, ASIAN, KAJARIA or equivalent approved make, colours & shades, except white, ivory, grey, fume red brown, laid on 20 mm thick cement mortar 1:4 (1 cement:4 coarse sand) including pointing the joints with white cement and matching pigments, etc. complete as per direction of Engineer-In-Charge at all floors and all heights.	sqm	26.37	1019.05	26874.13
8	Providing and fixing 1st quality Ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer) minimum thickness 5mm of NITCO, SOMANY, ASIAN, KAJARIA or equivalent approved make in all colours, shades except burgundy, bottle green, black of size 300x200 in skirting and dados over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per sqm including pointing in white cement mixed with pigment of matching shade complete as per direction of Engineer-In-charge. In all floors and all heights .	sqm	106.94	969.94	103729.78
9	Providing & Applying priming coat with Water base wall primer of approved brand and manufacture on plaster/putty surface as per the instruction of Engineer-In-Charge at all elevations and all heights including all material & labour complete.	sqm	1700.00	68.39	116263.00
10	Providing and applying white cement based putty of average thickness 1 mm of approved brand and manufacturer, over the plastered wall surfaces to prepare the surface even and smooth as per the instruction of Engineer-In-Charge at all elevations including all material & labour complete.	sqm	1700.00	70.92	120564.00
11	Providing and applying to outside walls with two or more coats of Anti-Fungal Weather coat water proofing paint including scaffolding and cleaning the surface before application of approved colour and manufacture as per specification, instruction of Engineer-In-charge at all elevations including all material labour complete.	sqm	700.24	86.94	60878.27
32	Preparing surface and painting at all height with two or more coats of interior Plastic Emulsion "Royale Shyne" of Asian Paints or equivalent of approved shade as per the instructions of the manufacturers; giving uniform shade etc in all heights of walls etc. including interior wall primer & providing scaffolding, cleaning, curing and supply of all materials and labour complete as per drawing, design and direction of Architect/Engineer-In-Charge.	sqm	695.51	93.90	65308.76

33	Providing & Painting with synthetic enamel paint of approved brand and manufacture to give an even shade as per the instruction of Engineer - In-Charge at all floors and all heights including all material & labour complete.	sqm	32.34	129.06	4173.93
34	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 sand : 6 graded stone aggregate 20mm nominal size) over 75mm bed of dry brick ballast 40mm nominal size well ramed, consolidated and grouted with fine sand and finishing the top smooth including shuttering at the edges, excavation and disposing of surplus earth with a lead of 100m.	sqm	44.16	616.94	27243.92
35	Providing and fixing 10-12 mm thick Teracotta Slope Tile for Slope roof, wall and similar locations where ever required in horizontal/vertical surfaces of required size of approved shade, colour and texture, with moulding edge & approved groove pattern etc. laid over 12mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand) with joints treated with white cement mixed with matching pigment, epoxy touch ups including rubbing, curing, moulding and polishing to give high gloss finish etc. complete as per direction of Engineer-in-charge. In all floors and all heights.	sqm	278.25	1104.07	307208.25
36	Providing wall paintings and different pattern, different shades of Mural Arts paintings of approved colours and designs over base coats of acrylic exterior emulsion paint having VOC (Volatile Organic Compound) content less than 50 grams/liter of Approved brand (Asian Paints) Berger weather coat exterior /apex exterior paint (Asian paints) or apex ultima paint and shade over priming coat after thoroughly brushing the surface to remove all dirt and remains of loose powdered materials, including cost and conveyance of all materials to work site and all operational, incidental, labour charges etc., complete for finished item of work.	sqm	25.67	748.00	19201.16

37	<p>Providing and fixing of Greenlam/equivalent Clades standard dimension of 1300mm x 3050mm of thickness 6mm. (WOOD FINISH) for fixing used Al. sub structure is made up of Aluminum box sections of 38x38x2mm the. and 38x75x2mm the. The section size 75x38 x2mm will be using on the vertical joint of the two panels. As per the standard procedures in riveting system. Spacing of two verticals should always be maintained at 600mm. MS Brackets are of two types. Wind load brackets and Dead load brackets of size 85x50x5mm the. and to be placed in 1500 mm intervals in vertical. Wind load brackets will have vertical slot and Dead load brackets will have horizontal slots. Thermal separators to be placed between MS brackets and concrete structure. Bimetallic separators to be placed between Al. sub structure and MS brackets. Brackets fixing with nylon fasteners or self tapping bolts. Aluminum grid frame fixing in between brackets by SS nut and bolts. After framing done the panels fixing started with maintaining 6mm horizontal and vertical gaps between one panels to another. For fixing of panels done by riveting. Rivet distance maintain</p>	sqm	43.94	8360.00	367338.40
38	<p>Providing and fixing False ceiling of 12mm thick gypsum board sheets inclusive of all hangers, edge members and other clips complete, with sheets fixed with proper Phillip fastner by power drills and joints duly finished ensuring level in line, complete with putty, primer and painting of approved make and colour . Cost includes cutouts for electrical fittings, materials, labour, T&P etc complete as per direction of the Engineer-in-charge.</p>	sqm	488.86	1604.00	784129.19
39	<p>Providing, fitting and fixing 450mm-600 width and 2100mm height storage unit as per detail drawings/design provided with drawers and shelves having openable shutters up to Height 1000-1200 mm and other part Open Rack Storage. Storage unit top, bottom & openable shutters are made out of 19mm thick block board and all horizontal & vertical members of drawers & shelves are 12mm thick ply (conforming to IS code :5509), all exposed areas finished with 1.0mm thick laminate of approved make & shade & inside areas finished with 0.5mm thick white laminate of approved make and</p>	sqm	16.80	13792.00	231705.60

40	Painting two coats with Water soluble weather coat paints of approved shade of approved make or equivalent over out side brick wall over a coat of primer, by means of brush to outside surface of new walls after scraping, cleaning the surface including all cost of materials, scaffolding, labour, watering &	sqm	26.60	137.30	3652.18
41	Filling with good earth of approved quality obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement of table 300-2.	sqm	13.89	752.14	10449.59
42	Supplying & Fixing of Pre Cast Kerb Stone of Size 600mm X 300 X 150mm OF m-30 GRADE OF approved MAKE, DESIGN, COLOUR AND SIZE MADE BY Block making machine with proper compaction fixed in required pattern etc. complete in all respect conforming to IS 5758:1984.	each	222.00	249.55	55400.10
43	Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to	sqm	1413.75	608.40	860126.72
44	Construction of granular sub-base (Grading III) by providing well graded material, spreading in uniform layers with grader on prepared surface, mixing by mix in place method with rotavator at OMC and compacting with smooth wheel roller to achieve the desired density, complete as per MORD Technical Specification Clause 401 as per direction of Engineer.	cum	271.35	2921.40	792711.37
45	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mix plant, carriage of mixed material by tipper to site, laying in uniform layers with paver in subbase/ base course on well prepared surface and compacting with vibratory roller to achieve the desired density as per Clause 406 of MoSRT&H	cum	203.51	3443.70	700826.70
46	Providing and laying of Cement Concrete (1:2:4) with 12mm size B,H,C,B,Gr chips of approved quality from quarry mixing in concrete mixer , lowering and compacting in proper thickness, watering & curing for the required period .including all cost of labour ,material, conveyance, royalties and taxes , sundries , T & P etc. but excluding the cost of centering and shuttering all complete as per the directions of Engineer-in-charge.	cum	18.14	7229.55	131172.96
47	Providing & laying Kota stone slab flooring of 16mm (average) thick over a 16mm thick based of cement mortar 1:4 to a proper slope, line and level including cutting to required size and shape, fixing at corners	cum	748.82	1114.40	834485.01
				SAY	1,43,17,900.00

(Rupees ONE CRORE FORTY THREE LAKH SEVENTEEN THOUSAND NINE HUNDRED) ONLY

Ch. S. Prasad
M. S. Prasad
RWS & S Circle
M. No. 8-12-2007
9/12/23
5-12-23

Jeepale
JE
Basudevpur Block
21.11.23

Amish
21.11.23
Asst. Executive Block
Basudevpur Block

S. K. Sahu
BDO 21.11.23
Basudevpur Block
Development Officer

21/11/23
Addl. Executive Officer
Zilla Pank.