

OFFICE OF THE PANCHAYAT SAMITI, BONTH

At/PO- Bonth, Dist- Bhadrak, PIN- 756114

E-mail id- ori-bonth@nic.in

Letter no. 2298...

Date. 23.09.24..

DETAIL TENDER CALL NOTICE 01/BDO,BONTH OF 2024-25

The Block Development Officer, Bonth invites a sealed percentage rate tender in single cover system on behalf of Governor of Odisha from registered & eligible class of Civil contractor of the state P W D (R&B) / Water resource / Rural Works / M.I/C.P.W.D for the following works. **The Block Development Officer, Bonth reserves the right to reject any or all the tenders without assigning any reason thereof.** Other details can be seen in Annexure-1.

Term & Condition

- 1. Cost of Tender Paper :-** The Tender Specification can be obtained from & payment towards the cost of Tender papers as mentioned (Non- Refundable) in shape of Demand Draft /Term Deposit to be drawn in favour of Block Development Officer, Bonth in any Nationalized Bank having its branch at Bhadrak on any working day on or of from 25.09.2024 to 08.10.2024 for the above work.
- 2. Date of receipt and mode of submission of Tender Papers:-** The tender papers have to be submitted as sealed tender papers in complete shape through Registered Post/ Speed Post only, directly sending it to the BDO Bonth in his official postal address. The last date of receipt of tender paper is 08.10.2024 upto 1.00 PM. The undersigned will not be responsible for postal delay if any non-receipt of the tender papers in time. **The bidders must super scribe the name of the work/project on the sealed envelope.**
- 3. Date of Opening of Tender Paper:-**The tender paper shall be opened on 08.10.2024 at 3.30 PM in the presence of the bidders or in their authorized representative having written authorization for the purpose before the tender committee in the conference Hall of Bonth Block Office.
- 4. Documents to be attached:-**The following documents should be furnished with the tender paper failing which the tender will be liable for rejection.
 - (A) Self attested copy of contractor Registration Certificate.
 - (B) Self attested copy of PAN card/Certificate of GSTIN.
 - (C) Demand Draft/Term Deposit Receipt of Paper Cost & EMD.
 - (D) Self attested copy of caste certificate issued by competent authorities in case of SC/ST Contractors desirous of availing preference.
 - (E) The bidders must produce an original affidavit in support of the authenticity of documents attached with the tender papers.
 - (F) Joint venture consortium agreements are not allowed to participate tender.
- 5. Shortfall of any required documents and tender paper is liable for rejection.**


Block Development Officer
Bonth

6. **E.M.D @1%** of tender value shall be pledged in favour of Block Development Officer along with the bids
7. **Additional Performance Security Deposit:-** The affidavit in support of APS will be submitted by the successful bidder for the cost of less quoted in percentage of the amount put to tender before signing of the agreement of the contract.(Vide works Department letter No-16659/W dated-20.09.2022 Govt. of Odisha, Works Department) As per office memorandum No-6559 dated-06.06.2021 of Works Deptt., Govt. of Odisha modification to APS will be followed as detailed below:

SI NO.	Range of Difference between the estimated cost put to tender & Bid amount	Additional performance Security to be deposited by the successful Bidder
1	Below 5%	No additional Performance Security
2	From 5% & above & below 10%	50% of (Difference between estimated cost put to tender & Bid amount)
3	From 10% & above	150% of (Difference between estimated cost put to tender & Bid amount)


8. Submission of more than one tender paper by bidder for a single work will be liable for rejection of all such tender papers.
9. **The Block Development Officer, Bonth reserves the right to reject any or all the tenders without assigning any reason thereof .Other details can be seen in the bidding documents.**
10. If rate quoted by the bidder is less than 15% of the amount put to tender, then such a bid shall be rejected & all the tenders shall be finalized basing of merits of rest bids. But if more than one bid is quoted (decimal upto two numbers will be taken for all practical purposes) either all the estimated cost put to tender or less than the estimated cost put to tender, the tender accepting authority will finalize the tender through a transparent lottery system, where all bidders/ their authorized representative, the concerned SE/Executive Engineer of concerned Division DAO will remain present vide works Deptt O.M No- 1437 dated-31/01/2023
11. **No Tender paper shall be received through Drop Box or Courier Services & tender paper received through Drop Box or Courier Services shall be liable for rejection.**


 Block Development Officer
 Bonth

Memo No- 2899

Date- 23.09.24

Copy submitted to the Director, I & PR, Govt. of Odisha, Bhubaneswar for favour of kind information.


23/9/24
Block Development Officer
Bonth

Memo No- 2900

Date- 23.09.24


Copy Submitted to The Collector & DM, Bhadrak / CDO-cum-EO, ZP, Bhadrak/ DWO, Bhadrak/ District Planning Officer, Bhadrak /D.I & P.R.O, Bhadrak for favour of kind information & necessary action.


23/9/24
Block Development Officer
Bonth

Memo No.- 2901

Date- 23.09.24

Copy forwarded to EE, Bhadrak/ EE, R.W.S & S, Bhadrak, EE R & B Divison, Bhadrak/ EE,M.I. Divison, Bhadrak/EE,R.W Divison, Bhadrak/ All BDOs of Bhadrak District/ Tahasildar, Bonth/ IIC, Bonth, Bonth PS/ CDPO, ICDS, Bonth for information & necessary action with request to display in their Notice board for wide circulation.


23/9/24
Block Development Officer
Bonth

Memo No- 2902

Date- 23.09.24

Copy forwarded to The DeGM, Bhadrak for information with a request to upload the detail tender call notice, tender schedule and the bid documents in the official website of Bhadrak i.e <http://bhadrak.odisha.gov.in>


23/9/24
Block Development Officer
Bonth

Memo No- 2903.

Date- 23.09.24

Copy to Office Notice Board & C.P,Bonth Block to assist for uploading the DTCN & bid documents at NIC, Bhadrak.


23/9/24
Block Development Officer
Bonth

Annexure-1

BID IDENTIFICATION NUMBER	NAME OF THE WORK	APPROXI. EST COST PUT TO TENDER	CLASS OF CONTRACTOR	EMD(1%) Approx.	COST OF TENDER PAPER	TIME OF COMPLETION
2	3	4	5	6	7	8
PSB-01/2024-25	Const. of Additional Classroom at Budhijagulai Govt. UP school, Biridihi, Anijo GP	Rs. 12,52,469	'C' & 'D'	Rs.15,470	Rs.6,000/-	SIX CALENDAR MONTH
PSB-02/2024-25	Const. of Additional Classroom at Kausalya Nodal School, Rampur GP	Rs. 12,09,255	'C' & 'D'	Rs.12,092	Rs.6,000/-	SIX CALENDAR MONTH
PSB-03/2024-25	Const. of Additional Classroom at Kandaba Nodal School, Gopinathpur GP	Rs. 12,07,338	'C' & 'D'	Rs.12,073	Rs.6,000/-	SIX CALENDAR MONTH
PSB-04/2024-25	Const. of Additional Classroom at Khageswar High School, Chhayalsingh GP	Rs.13,32,602	'C' & 'D'	Rs.13,326	Rs.6,000/-	SIX CALENDAR MONTH
PSB-05/2024-25	Const. of Additional Classroom at Bankitira High School, Kadabaranga GP	Rs.13,35,585	'C' & 'D'	Rs.13,355	Rs.6,000/-	SIX CALENDAR MONTH


 23/3/2024
 Block Development Officer
 Bonth Bonth

TENDER SCHEDULE

Name of the work :- Const. of additional classroom at Budhijagulai Govt. UP School, Bridayal at Anijo -GP, Block-Bonth, Dist-Bhadrak

Tender Schedule Cost :- ₹ 12,56,183.00 12,52,469

Sl.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
					(Rs.)
Part - A Civil Cost)					
1	Foundation excavation in hard soil including levelling and dressing the bed and sides depositing muck within initial lead and lift etc. complete as per direction of Engg-In-Charge .	0.750	Cum.	269.70	202.28
2	Filling foundation and plinth with sand and well watered and rammed including cost, conveyance and royalty etc complete as per direction of Engg.-in-Charge.	42.420	Cum.	1,100.49	46,682.79
3	Cement concrete (1:3:6)with 40mm size CBHG metal including cost, conveyance and royalty etc. complete as per direction of Engg.-in-Charge.	8.770	Cum.	6,485.05	56,873.89
4	Fly Ash Brick masonry in c.m. 1:6 in F & P including cost,conveyance and royalty of materials curing etc. complete. as per the direction of the Engineer-in-charge.	5.260	Cum.	5,834.96	30,691.89
5	1" thick D.P.C with C.C(1:2:4) using 12mm. Chips etc. cpmplete as per direction of Engg-in-Charge .	14.955	Sqm	369.10	5,519.89
6	1st class Fly Ash brick masonry work in superstructure thoroughly soaked in water, with cement mortar (1:6) including scaffoldings ,racking out joints, curing etc complete as per specification/drawing and as per the direction of the Engineer-in-charge.				
	i Ground Floor Floor	33.030	Cum.	5,868.29	1,93,829.62
7	R.C.C. work M20 grade using 20mm.and down grade HBG crusher broken chips including hoisting,laying, cost,conveyance and royalty of materials curing including centering and shuttering etc. complete as per direction of Engg-in-Charge .				
	i Beam & Column	8.720	Cum.	16,130.56	1,40,658.48
	a Ground Floor				
	ii 65mm avg. Chajja	16.098	Sqm.	1,243.54	20,018.51
	a Ground Floor				

Sl.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT (Rs.)
	iii Roof Slab				
	a Ground Floor	10.750	Cum.	14,024.92	1,50,767.89
	iv Lintel				
	a Ground Floor	2.490	Cum.	14,615.28	36,392.05
	v Staircase				
	a Ground Floor	2.520	Cum.	16,009.62	40,344.24
8	Supplying, fitting and placing uncoated HYSD bar reinforcement complete in proper position including cost of binding wire 18 to 20 gauge as per direction of Engg.-in-Charge. (SAIL/TATA/TISCO/INDAL/SHYAM)				
	i Ground Floor	24.650	Ql	9,033.94	2,22,686.62
9	12mm cement plaster in cement mortar (1:6) including necessary scaffolding curing etc. as per direction of Engg.-in-Charge.				
	i Ground Floor	131.830	Sqm	193.17	25,465.60
10	16mm thick cement plaster in cement mortar (1:6) including necessary scaffolding curing etc. as per direction of Engg.-in-Charge.				
	i Ground Floor	196.070	Sqm	276.92	54,295.70
11	6mm.thick cement plaster with C.M(1:4) to RCC surface including closed deep chipping and slury treatment etc. complete as per direction of Engg.-in-Charge.				
	i Ground Floor	126.790	Sqm	212.49	26,941.61
12	Fixing Vitrified tiles in floors of size 600mm x600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar (1:4) and filling joints with white cement of approved quality including cost of all materials, labour T&P etc required for the work all complete as per direction of Engineer-in-charge.				
	i Ground Floor	74.990	Sqm	1,142.72	85,692.57
13	Fixing Vitrified tiles in dados skirting and risers of stepson 12 mm thick cement plaster(1:3) jointed with neat cement slurry mixed with pigments to matche shade of the tiles including rubbing and polishing complete as per direction of Engineer-in-charge.				
	i Ground Floor	9.900	Sqm	1,301.05	12,880.40

DESCRIPTION

DESCRIPTION	QTY	UNIT	RATE	AMOUNT
				(Rs.)
Supplying, fitting and fixing of MS steel shutter with frame with MS angle frame of 35x35x6mm and shutter section of 30x30x5mm MS angle with welding of 25x6mm flat and welding of 16 gauge CR sheet with arrangement of clamp, fitting of 3 nos of 4" hinges and 300mm x 16 mm MS aldrop with 8" Tower bolt including cost, conveyance, and taxes of all materials, labour, T&P etc required for complete in all respect.				
(i) All Floors	893 170	Kg	99 30	0,88,691.78
15 Enamel Painting two coats with enamel paint over one coat of primer of approved quality etc. complete as per direction of Engg-in-Charge.				
i Ground Floor	53.250	Sqm	259.78	13,833.29
G. Total				12,52,469.00

Approved 15 items only (Rupees twelve lakhs fifty ^{two} thousand one ~~hundred~~ hundred eightythree) only
 sixty nine.


Junior Engineer
 Bonth Block


 30.07.2024
 Asst. Executive Engineer
 Assistant Engineer
 Bonth Block



Block Development Officer
 Bonth Block

My / our quoted rate is _____ % (both in figure and words) excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer
 No. of Correction:
 No. of over writing:
 No. of interpolation:


 Addl. Executive Officer (Tech.)
 Zilla Parishad, Bhadrak

TENDER SCHEDULE

Name of the work :- Construction of additional Class Room at Kaushalya Nodal School at Rampur -GP, Block-Bonth, Dist-Bhadrak

Tender Schedule Cost :- ₹ ~~12,11,167.00~~ 12,09,255

Sl.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
					(Rs.)
Part - A Civil Cost)					
1	Foundation excavation in hard soil including levelling and dressing the bed and sides depositing muck within initial lead and lift etc. complete as per direction of Engg-in-Charge .	14.650	Cum.	269.70	3,951.11
2	Filling foundation and plinth with sand and well watered and rammed including cost, conveyance and royalty etc complete as per direction of Engg.-in-Charge.	28.140	Cum.	988.28	27,810.20
3	Cement concrete (1:3:6)with 40mm size CBHG metal including cost, conveyance and royalty etc. complete as per direction of Engg.-in-Charge.	7.630	Cum.	6,341.99	48,389.38
4	Fly Ash Brick masonry in c.m. 1:6 in F & P including cost,conveyance and royalty of materials curing etc. complete. as per the direction of the Engineer-in-charge.	8.500	Cum.	6,063.84	51,542.64
5	1" thick D.P.C with C.C(1:2:4) using 12mm. Chips etc. cpmplete as per direction of Engg-in-Charge .	8.988	Sqm	365.63	3,286.10
6	1st class Fly Ash brick masonry work in superstructure thoroughly soaked in water, with cement mortar (1:6) Including scaffoldings ,racking out joints, curing etc complete as per specification/drawing and as per the direction of the Engineer-in-charge.				
	i Ground Floor Floor	14.940	Cum.	6,097.17	91,091.72
7	R.C.C. work M20 grade using 20mm.and down grade HBG crusher broken chips including hoisting,laying, cost,conveyance and royalty of materials curing including centering and shuttering etc. complete as per direction of Engg-in-Charge .				
	i Column Base				
	a Ground Floor	5.500	Cum.	6,887.47	37,881.09
	ii Plinth Beam / Tie Beam				
	a Ground Floor	1.510	Cum.	7,757.50	11,713.83
	iii Beam & Column				

Sl. No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
					(Rs.)
a	Ground Floor	5.740	Cum	15,996.44	0,91,819.57
iv	65mm avg. Chajja				
a	Ground Floor	10.800	Sqm	1,234.82	13,338.06
v	Roof Slab				
a	Ground Floor	7.350	Cum	13,890.80	1,02,097.38
vi	Lintel				
a	Ground Floor	1.700	Cum.	14,481.16	24,617.97
8	Single under reamed pile foundation with RCC M20 using 25mm and down graded size black hard granite (Crusher broken) stone chips including cost of boring but excluding cost of M.S./Tor steel and labour charges for cutting, bending and binding of steel. etc. complete 300mm pile - 5.00m long	20	Pile	5,158.56	1,03,171.13
9	Supplying, fitting and placing uncoated HYSD bar reinforcement complete in proper position including cost of binding wire 18 to 20 gauge as per direction of Engg.-in-Charge.				
i	Ground Floor	34.160	Qtl	9,033.94	3,08,599.39
10	12mm cement plaster in cement mortar (1:6) including necessary scaffolding curing etc. as per direction of Engg.-in-Charge.				
i	Ground Floor	91.530	Sqm	191.49	17,527.08
11	16mm thick cement plaster in cement mortar (1:6) including necessary scaffolding curing etc. as per direction of Engg.-in-Charge.				
i	Ground Floor	98.800	Sqm	274.90	27,160.12
12	6mm.thick cement plaster with C.M(1:4) to RCC surface including closed deep chipping and slury treatment etc. complete as per direction of Engg.-in-Charge.				
i	Ground Floor	77.860	Sqm	211.65	16,415.57
13	Fixing Vitrified tiles in floors of size 600mm x600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar (1:4)and filling joints with white cement of approved quality including cost of all materials, labour T&P etc rrequired for the work all completeas per direction of Engineer-in-charge.				
i	Ground Floor	47.860	Sqm	1,143.67	54,736.05

Sl. No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
					(Rs.)
14	Fixing Vitrified tiles in dados skirting and risers of stepson 12 mm thick cement plaster(1:3) jointed with neat cement slurry mixed with pigments to matche shade of the tiles including rubbing and polishing complete as per direction of Engineer-In-charge.				
	i Ground Floor	5.200	Sqm	1,302.67	6,773.88
15.	Wall Priming one coats on now work with wall water bound primer of approved shade as per direction of Engg-in-Charge .				
	i Ground Floor	262.690	Sqm	76.49	20,093.16
16.	Wall painting two coats on new work with Plastic Emulsion Paint of approved shade etc. complete as per direction of Engg-in-Charge .				
	i Ground Floor	146.260	Sqm	107.28	15,690.77
17.	Finishing wall surface of walls with Acrylic wall putty (Water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes, labour T & P etc. complete as per direction of Engg-in-Charge .				
	i Ground Floor	146.260	Sqm	89.60	13,104.90
18.	Wall painting two coats on new work with Weather coat paint of approved shade as per direction of Engg.-in-Charge.				
	i Ground Floor	116.430	Sqm	96.92	11,283.81
19.	Supplying ,fitting and fixing of MS steel shutter with frame with MS angle frame of 35x35x6mm and shutter section of 30x30x5mm MS angle with welding of 25x6mm flat and welding of 16 gauge CR sheet witharrangement of clamp, fitting of 3 nos of 4" hinges and 300mm x16 mm MS aldrop with 8" Tower bolt including cost, conveyance, and taxes of all materials, labour , T&P etc required for complete in all respect.				
	(i) All Floors	478.080	Kg.	99.30	47,473.34
20	Enamel Painting two coats with enamel paint over one coat of primer of approved quality etc. complete as per direction of Engg-in-Charge .				
	i Ground Floor	29.160	Sqm	259.78	7,575.18
21	20mm. thick grading plaster in c.m. 1:4 over roof slab and chujja including cost conveyance and royalty of materials curing etc. complete as per direction of Engg-in-Charge .				
	i Ground Floor	58.670	Sqm	299.99	17,660.12

DESCRIPTION	QTY	UNIT	RATE	AMOUNT
				(Rs.)
Supplying, fitting & fixing of stainless steel of 304 grade in Hand Railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm.x2mm. @ 0.90m. C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect etc. complete as per direction of Engg-in-Charge .	6.500	Ml.	3,588.31	23,324.02
23 Fixing Industrial Chequered tiles in floors, treads or steps and landings on 25 mm thick CM (1:1) jointed with neat cement slurry mixed with pigments to match the shades including cost for rubbing, polishing & cost of tiles etc. complete as per direction of Engg-in-Charge .				
(i) Ground Floor	11.340	Sqm.	981.47	11,129.87
			G. Total	12,09,255.00

Approved 23 items only (Rupees twelve lakhs eleven thousand one hundred ~~sixty seven~~ ^{five} only)

[Signature]
30/07/24
Junior Engineer
Booth Block

[Signature]
30.07.2024
Asst. Executive Engineer
Booth Block

[Signature]
Block Development Officer
Booth Block

My / our quoted rate is _____ % (both in figure and words) excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:

[Signature]
Addl. Executive Officer (Tech.)
Zilla Parishad, Bhadrak

TENDER SCHEDULE

Name of the work :- Construction of additional Class Room at Kandaba Nodal School at Gopinathpur -GP, Block-Bonth, Dist-Bhadrak

Tender Schedule Cost :- ₹ (12,11,411.00) 12,07,338

Sl.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
					(Rs.)
Part - A Civil Cost)					
1	Foundation excavation in hard soil including levelling and dressing the bed and sides depositing muck within initial lead and lift etc. complete as per direction of Engg-in-Charge .	14.650	Cum.	269.70	3,951.11
2	Filling foundation and plinth with sand and well watered and rammed including cost, conveyance and royalty etc complete as per direction of Engg.-in-Charge.	28.140	Cum.	1,054.03	29,660.40
3	Cement concrete (1:3:6)with 40mm size CBHG metal including cost, conveyance and royalty etc. complete as per direction of Engg.-in-Charge.	7.630	Cum.	6,418.15	48,970.48
4	Fly Ash Brick masonry in c.m. 1:6 in F & P including cost,conveyance and royalty of materials curing etc. complete. as per the direction of the Engineer-in-charge.	8.500	Cum.	5,821.95	49,486.58
5	1" thick D.P.C with C.C(1:2:4) using 12mm. Chips etc. cpmplete as per direction of Engg-in-Charge .	8.988	Sqm	367.47	3,302.64
6	1st class Fly Ash brick masonry work in superstructure thoroughly soaked in water, with cement mortar (1:6) including scaffoldings ,racking out joints, curing etc complete as per specification/drawing and as per the direction of the Engineer-in-charge.				
	i Ground Floor Floor	14.940	Cum.	5,855.28	87,477.88
7	R.C.C. work M20 grade using 20mm.and down grade HBG crusher broken chips including hoisting,laying, cost,conveyance and royalty of materials curing including centering and shuttering etc. complete as per direction of Engg-in-Charge .				
	i Column Base				
	a Ground Floor	5.500	Cum.	6,958.87	38,273.79
	ii Plinth Beam / Tie Beam				
	a Ground Floor	1.510	Cum.	7,828.90	11,821.64
	iii Beam & Column				

Sl. No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
					(Rs.)
	a Ground Floor	5 740	Cum	16,067.84	0,92,229.40
	iv 65mm avg. Chajja	10 800	Sqm	1,239.47	13,386.28
	a Ground Floor				
	v Roof Slab	7.350	Cum	13,962.20	1,02,622.17
	a Ground Floor				
	vi Lintel	1.700	Cum	14,552.56	24,739.35
	a Ground Floor				
8	Single under reamed pile foundation with RCC M20 using 25mm and down graded size black hard granite (Crusher broken) stone chips including cost of boring but excluding cost of M.S./Tor steel and labour charges for cutting, bending and binding of 300mm pile - 5.00m long	20	Pile	5,191.75	1,03,835.00
9	Supplying, fitting and placing uncoated HYSD bar reinforcement complete in proper position including cost of binding wire 18 to 20 gauge as per direction of Engg.-in-Charge. (SAIL/TATA TISCON/JINDAL/SHYAM)	34.160	Qtl	9,033.94	3,08,599.39
	i Ground Floor				
10	12mm cement plaster in cement mortar (1:6) including necessary scaffolding curing etc. as per direction of Engg.-in-Charge.	91.530	Sqm	192.47	17,616.78
	i Ground Floor				
11	16mm thick cement plaster in cement mortar (1:6) including necessary scaffolding curing etc. as per direction of Engg.-in-Charge.	98.800	Sqm	276.08	27,276.70
	i Ground Floor				
12	6mm.thick cement plaster with C.M(1:4) to RCC surface including closed deep chipping and slury treatment etc. complete as per direction of Engg.-in	75.170	Sqm	212.15	15,947.32
	i Ground Floor				
13	Fixing Vitrified tiles in floors of size 600mm x600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar (1:4)and filling joints with white cement of approved quality including cost of all materials, labour T&P etc rrequired for the work all completeas per direction of Engineer-in charge.	47.860	Sqm	1,141.75	54,644.16
	i Ground Floor				

DESCRIPTION		QTY	UNIT	RATE	AMOUNT (Rs.)
14	Fixing Vitrified tiles in dados skirting and risers of stepson 12 mm thick cement plaster(1:3) jointed with neat cement slurry mixed with pigments to matche shade of the tiles including rubbing and polishing complete as per direction of Engineer-in-charge.				
	i Ground Floor	5.200	Sqm	1,300.35	6,761.82
15	Wall Priming one coats on new work with wall water bound primer of approved shade as per direction of Engg-in-Charge .				
	i Ground Floor	260.300	Sqm	76.49	19,910.35
16	Wall painting two coats on new work with Plastic Emulsion Paint of approved shade etc. complete as per direction of Engg-in-Charge .				
	i Ground Floor	143.870	Sqm	107.28	15,434.37
17	Finishing wall surface of walls with Acrylic wall putty (Water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes, labour T & P etc. complete as per direction of Engg-in-Charge .				
	i Ground Floor	143.870	Sqm	89.60	12,890.75
18	Wall painting two coats on new work with Weather coat paint of approved shade as per direction of Engg.-in-Charge.				
	i Ground Floor	116.430	Sqm	96.92	11,283.81
19	Supplying ,fitting and fixing of MS steel shutter with frame with MS angle frame of 35x35x6mm and shutter section of 30x30x5mm MS angle with welding of 25x6mm flat and welding of 16 gauge CR sheet witharrangement of clamp, fitting of 3 nos of 4" hinges and 300mm x16 mm MS aldrop with 8" Tower bolt including cost, conveyance, and taxes of all materials, labour , T&P etc required for complete in all respect.				
	(i) All Floors	478.080	Kg.	99.30	47,473.34
20	Eamel Painting two coats with enamel paint over one coat of primer of approved quality etc. complete as per direction of Engg-in-Charge .				
	i Ground Floor	29.160	Sqm	259.78	7,575.18
21	20mm. thick grading plaster in c.m. 1:4 over roof slab and chujja including cost conveyance and royalty of materials curing etc. complete as per direction of Engg-in-Charge .				
	i Ground Floor	58.870	Sqm	301.37	17,741.36

DESCRIPTION	QTY	UNIT	RATE	AMOUNT
				(Rs.)
Supplying, fitting & fixing of stainless steel of 304 grade in Hand Railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm.x2mm. @ 0.90m. C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect etc. complete as per direction of Engg-in-Charge .	6.500	MI.	3.588 31	23,324 02
23 Fixing industrial Chequered tiles in floors, treads or steps and landings on 25 mm thick CM (1:1) jointed with neat cement slurry mixed with pigments to match the shades including cost for rubbing, polishing & cost of tiles etc. complete as per direction of Engg-in-Charge .	11.340	Sqm.	979.02	11,102.09
(i) Ground Floor			G. Total	12,07,338.00

Approved 23 items only (Rupees twelve lakhs eleven thousand four hundred eleven only)

[Signature]
30.7.24
Junior Engineer
Bonth Block

[Signature]
30.07.2024
Asst. Executive Engineer
Assistant Exe. Engineer
Bonth Block

[Signature]
Block Development Officer
Bonth Block

My / our quoted rate is _____ % (both in figure and words) excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer
No. of Correction:
No. of over writing:
No. of interpolation:

[Signature]
Addl. Executive Officer (Tech.)
Zilla Parishad, Bhadrak

TENDER SCHEDULE

Name of the work :- Const. of additional classroom at Khageswar High School, Chhayalsingh, GP-Chhayalsingh, Block-Bonth, Dist-Bhadrak

Tender Schedule Cost :- ₹ (13,34,318.00) 13,32,602

Sl.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
					(Rs.)
Part - A Civil Cost)					
1	Foundation excavation in hard soil including levelling and dressing the bed and sides depositing muck within initial lead and lift etc. complete as per direction of Engg-in-Charge.	15.700	Cum.	269.70	4,234.29
2	Filling foundation and plinth with sand and well watered and rammed including cost, conveyance and royalty etc complete as per direction of Engg.	30.480	Cum.	1,054.03	32,126.83
3	Cement concrete (1:3:6)with 40mm size CBHG metal including cost, conveyance and royalty etc. complete as per direction of Engg.-in-Charge.	8.770	Cum.	6,462.75	56,678.32
4	Fly Ash Brick masonry in c.m. 1:6 in F & P including cost, conveyance and royalty of materials curing etc. complete. as per the direction of the Engineer-in-charge.	9.370	Cum.	5,821.95	54,551.67
5	1" thick D.P.C with C.C(1:2:4) using 12mm. Chips etc. complete as per direction of Engg-in-Charge.	9.738	Sqm	368.54	3,588.66
6	1st class Fly Ash brick masonry work in superstructure thoroughly soaked in water, with cement mortar (1:6) including scaffoldings, racking out joints, curing etc complete as per specification/drawing and as per the direction of the Engineer-in-charge.				
	i Ground Floor Floor	16.710	Cum.	5,855.28	97,841.73
7	R.C.C. work M20 grade using 20mm. and down grade HBG crusher broken chips including hoisting, laying, cost, conveyance and royalty of materials curing including centering and shuttering etc. complete as per direction of Engg-				
	i Column Base				
	a Ground Floor	5.500	Cum.	7,000.69	38,503.80
	ii Plinth Beam / Tie Beam				
	a Ground Floor	1.740	Cum.	7,870.72	13,695.05
	iii Beam & Column				
	a Ground Floor	5.600	Cum.	16,109.66	0,90,214.10

Sl.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
					(Rs.)
		0 000	Cum	18,409.57	
b	First Floor (Head Room)				
iv	65mm avg. Chajja	11 400	Sqm	1,242 18	14,160 85
a	Ground Floor				
v	Roof Slab	8.600	Cum.	14,004.02	1,20,434.57
a	Ground Floor				
vi	Lintel	1.880	Cum.	14,594.38	27,437.43
a	Ground Floor				
8	Single under reamed pile foundation with RCC M20 using 25mm and down graded size black hard granite (Crusher broken) stone chips including cost of boring but excluding cost of M.S./Tor steel and labour charges for cutting, bending and binding of steel. etc. complete 300mm pile - 5.00m long	20	Pile	5,211.20	1,04,224.02
9	Supplying, fitting and placing uncoated HYSD bar reinforcement complete in proper position including cost of binding wire 18 to 20 gauge as per direction of Engg.-in-Charge. (SAIL/TATA TISCON/LINDAL/SHYAM)	35.560	Qll	9,033.94	3,21,246.91
i	Ground Floor				
10	12mm cement plaster in cement mortar (1:6) including necessary scaffolding curing etc. as per direction of Engg.-in-Charge.	103.200	Sqm	192.47	19,862.90
i	Ground Floor				
11	16mm thick cement plaster in cement mortar (1:6) including necessary scaffolding curing etc. as per direction of Engg.-in-Charge.	111.100	Sqm	276.08	30,672.49
i	Ground Floor				
12	6mm.thick cement plaster with C.M(1:4) to RCC surface including closed deep chipping and slury treatment etc. complete as per direction of Engg.-in-Charge.	87.970	Sqm	212.15	18,662.84
i	Ground Floor				
13	Fixing Vitrified tiles in floors of size 600mm x600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar (1:4) and filling joints with white cement of approved quality including cost of all materials, labour T&P etc required for the work all complete as per direction of Engineer-in-charge.	56.840	Sqm	1,141.75	64,897.07
i	Ground Floor				

DESCRIPTION	QTY	UNIT	RATE	AMOUNT
				(Rs.)
14 Fixing Vitrified tiles in dados skirting and risers of stepson 12 mm thick cement plaster(1:3) jointed with neat cement slurry mixed with pigments to matche shade of the tiles including rubbing and polishing complete as per direction of Engineer-in-charge.	5.730	Sqm	1,300.35	7,451.01
i Ground Floor				
15. Wall Priming one coats on new work with wall water bound primer of approved shade as per direction of Engg-in-Charge .	296.540	Sqm	81.08	24,043.45
i Ground Floor				
16. Wall painting two coats on new work with Plastic Emulsion Paint of approved shade etc. complete as per direction of Engg-in-Charge .	167.240	Sqm	107.28	17,941.51
i Ground Floor				
17. Finishing wall surface of walls with Acrylic wall putty (Water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes, labour T & P etc. complete as per direction of Engg-in-Charge	167.240	Sqm	89.60	14,984.70
i Ground Floor				
18. Wall painting two coats on new work with Weather coat paint of approved shade as per direction of Engg.-in-Charge.	129.300	Sqm	96.92	12,531.11
i Ground Floor				
19. Supplying ,fitting and fixing of MS steel shutter with frame with MS angle frame of 35x35x6mm and shutter section of 30x30x5mm MS angle with welding of 25x6mm flat and welding of 16 gauge CR sheet witharrangement of clamp, fitting of 3 nos of 4" hinges and 300mm x16 mm MS aldrop with 8" Tower bolt including cost, conveyance, and taxes of all materials, labour , T&P etc required for complete in all respect.	478.080	Kg.	99.30	47,473.34
(i) All Floors				
20 Enamel Painting two coats with enamel paint over one coat of primer of approved quality etc. complete as per direction of Engg-in-Charge .	29.160	Sqm	259.78	7,575.18
i Ground Floor				
21 20mm. thick grading plaster in c.m. 1:4 over roof slab and chujja including cost conveyance and royalty of materials curing etc. complete as per direction of Engg-In-Charge .	68.850	Sqm	301.37	20,748.98
i Ground Floor				

DESCRIPTION	QTY	UNIT	RATE	AMOUNT
				(Rs.)
22 Supplying, fitting & fixing of stainless steel of 304 grade in Hand Railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm.x2mm. @ 0.90m. C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect etc. complete as per direction of Engg-In-Charge .	15.200	Mt.	3,588.31	54,542.31
23 Fixing Industrial Chequered tiles in floors, treads or steps and landings on 25 mm thick CM (1:1) jointed with neat cement slurry mixed with pigments to match the shades including cost for rubbing, polishing & cost of tiles etc. complete as per direction of Engg-In-Charge .				12,275.91
(i) Ground Floor	12.540	Sqm.	979.02	
			G. Total	13,32,602.00

Approved 23 (twentythree) items only (Rupees thirteen lakhs ^{two} ~~thirty four~~ thousand ^{two} ~~three~~ hundred ^{two} ~~eighteen~~ only)

[Signature]
 20/7/24
 Junior Engineer
 South Block

[Signature]
 30.07.2024
 Asst. Executive Engineer
 South Block

[Signature]
 Block Development Officer
 South Block

My / our quoted rate is _____ % (both in figure and words) excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer
 No. of Correction:
 No. of over writing:
 No. of interpolation:

[Signature]
 Addl. Executive Engineer (Tech.)
 Zilla Parishad, Bhadrak

TENDER SCHEDULE

Name of the work - Const. of additional classroom at Bankitira High School, Kadabaranga, Block-Bonth, Dist-Bhadrak

Tender Schedule Cost :- ₹ 13,37,301.00 19,35,585

Sl.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
					(Rs.)
Part - A Civil Cost)					
1	Foundation excavation in hard soil including levelling and dressing the bed and sides depositing muck within initial lead and lift etc. complete as per direction of Engg-in-Charge .	15.700	Cum	269.70	4,234.29
2	Filling foundation and plinth with sand and well watered and rammed including cost, conveyance and royalty etc complete as per direction of Engg.-	30.480	Cum.	1,100.49	33,542.94
3	Cement concrete (1:3:6)with 40mm size CBHG metal including cost, conveyance and royalty etc. complete as per direction of Engg.-in-Charge.	8.770	Cum.	6,485.05	56,873.89
4	Fly Ash Brick masonry in c.m. 1:6 in F & P including cost,conveyance and royalty of materials curing etc. complete. as per the direction of the Engineer-in-charge.	9.370 9.370	Cum.	5,834.96	54,673.58
5	1" thick D.P.C with C.C(1:2:4) using 12mm. Chips etc. complete as per direction of Engg-in-Charge .	9.738	Sqm	369.10	3,594.11
6	1st class Fly Ash brick masonry work in superstructure thoroughly soaked in water, with cement mortar (1:6) including scaffoldings ,racking out joints, curing etc complete as per specification/drawing and as per the direction of the Engineer-in-charge.				
	i Ground Floor Floor	16.710	Cum.	5,868.29	98,059.13
7	R.C.C. work M20 grade using 20mm.and down grade HBG crusher broken chips Including hoisting,laying, cost,conveyance and royalty of materials curing including centering and shuttering etc. complete as per direction of Engg-in-Charge .				
	i Column Base				
	a Ground Floor	5.500	Cum.	7,021.59	38,618.75
	ii Plinth Beam / Tie Beam				
	a Ground Floor	1.740	Cum.	7,891.62	13,731.42
	iii Beam & Column				
	a Ground Floor	5.600	Cum.	16,130.56	0.90,331.14
	iv 65mm avg. Chajja				


Sl.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT (Rs.)
a	Ground Floor	11 400	Sqm	1,243.54	14,175.36
v	Roof Slab				
a	Ground Floor	8 600	Cum	14,024.92	1,20,614.31
vi	Lintel				
a	Ground Floor	1 880	Cum	14,615.28	27,478.73
8	Single under reamed pile foundation with RCC M20 using 25mm and down graded size black hard granite (Crusher broken) stone chips including cost of boring but excluding cost of M.S./Tor steel and labour charges for cutting, bending and blinding of steel. etc. complete 300mm pile - 5.00m long	20	Pile	5,220.92	1,04,418.33
9	Supplying, fitting and placing uncoated HYSD bar reinforcement complete in proper position including cost of binding wire 18 to 20 gauge as per direction of Engg.-in-Charge. (SAIL/TATA TISCO/JINDAL/SHYAM)				
i	Ground Floor	35.560	Qll	9,033.94	3,21,246.91
10	12mm cement plaster in cement mortar (1:6) including necessary scaffolding curing etc. as per direction of Engg.-in-Charge.				
i	Ground Floor	103.200	Sqm	193.17	19,935.14
11	16mm thick cement plaster in cement mortar (1:6) including necessary scaffolding curing etc. as per direction of Engg.-in-Charge.				
i	Ground Floor	111.100	Sqm	276.92	30,785.81
12	6mm.thick cement plaster with C.M(1:4) to RCC surface including closed deep chipping and slury treatment etc. complete as per direction of Engg.-in				
i	Ground Floor	87.970	Sqm	212.49	18,692.75
13	Fixing Vitrified tiles in floors (Printed Series) of size 600mm x600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar (1:4) and filling joints with white cement of approved quality including cost of all materials, labour T&P etc rrequired for the work all complete as per direction of Engineer-in-charge.				
i	Ground Floor	56.840	Sqm	1,142.72	64,952.20

Sl.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
					(Rs.)
14	Fixing Vitrified tiles in dados (Printed Series) skirting and risers of stepson 12 mm thick cement plaster(1:3) jointed with neat cement slurry mixed with pigments to matche shade of the tiles including rubbing and polishing complete as per direction of Engineer-in-charge.				
	i Ground Floor	5730	Sqm	1,301.05	7,455.02
15	Wall Priming one coats on new work with wall water bound primer of approved shade as per direction of Engg-in-Charge .				
	i Ground Floor	296.540	Sqm	81.08	24,043.46
16.	Wall painting two coats on new work with Plastic Emulsion Paint of approved shade etc. complete as per direction of Engg-in-Charge .				
	i Ground Floor	167.240	Sqm	107.28	17,941.51
17.	Finishing wall surface of walls with Acrylic wall putty (Water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes, labour T & P etc. complete as per direction of Engg-in-Charge .				
	i Ground Floor	167.240	Sqm	89.60	14,984.70
18.	Wall painting two coats on new work with Weather coat paint of approved shade as per direction of Engg.-in-Charge.				
	i Ground Floor	129.300	Sqm	96.92	12,531.11
19.	Supplying ,fitting and fixing of MS steel shutter with frame with MS angle frame of 35x35x6mm and shutter section of 30x30x5mm MS angle with welding of 25x6mm flat and welding of 16 gauge CR sheet witharrangement of clamp, fitting of 3 nos of 4" hinges and 300mm x16 mm MS aldrop with 8" Tower bolt including cost, conveyance, and taxes of all materials, labour , T&P etc required for complete in all respect.				
	(i) All Floors	478.080	Kg.	99.30	47,473.34
20	Enamel Painting two coats with enamel paint over one coat of primer of approved quality etc. complete as per direction of Engg-in-Charge .				
	i Ground Floor	29.160	Sqm	259.78	7,575.18
21	20mm. thick grading plaster in c.m. 1:4 over roof slab and chujja including cost conveyance and royalty of materials curing etc. complete as per direction of Engg-in-Charge .				
	i Ground Floor	68.850	Sqm	302.34	20,815.76

Sl.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
					(Rs.)
22	Supplying, fitting & fixing of stainless steel of 304 grade in Hand Railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm.x2mm. @ 0.90m. C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect etc. complete as per direction of Engg-in-Charge .	15.200	Mt.	3,588.31	54,542.31
23	Fixing industrial Chequered tiles in floors, treads or steps and landings on 25 mm thick CM (1:1) jointed with neat cement slurry mixed with pigments to match the shades including cost for rubbing, polishing & cost of tiles etc. complete as per direction of Engg-In-Charge .	12.540	Sqm.	979.62	12,284.43
(i)	Ground Floor				
G. Total					13,35,585.00

Approved 23 items only (Rupees thirteen lakhs ^{five} ~~thirty~~ thousand ^{one} ~~three~~ hundred ^{one} ~~one~~ only)


Junior Engineer
 Bonth Block


 30.07.2024
Assistant Executive Engineer
 Bonth Block


Block Development Officer
 Bonth Block

My / our quoted rate is _____ % (both in figure and words) excess over / less than / equal to the above estimated cost.

NOTES:


1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:


Addl. Executive Officer (Tech.)
 Zilla Parishad, Bhadrak