

OFFICE OF THE PANCHAYAT SAMITI, BONTH

At/PO- Bonth, Dist- Bhadrak, PIN- 756114

E-mail id- ori-bonth@nic.in

Letter no..3290.....

Date.28.10.2024.

DETAIL RE-TENDER CALL NOTICE 01/BDO,BONTH OF 2024-25

The Block Development Officer, Bonth invites a sealed percentage rate tender in single cover system on behalf of Governor of Odisha from registered & eligible class of Civil contractor of the state P W D (R&B) / Water resource / Rural Works / M.I/C.P.W.D for the following works. **The Block Development Officer, Bonth reserves the right to reject any or all the tenders without assigning any reason thereof.** Other details can be seen in Annexure-1.

Term & Condition

- 1. Cost of Tender Paper :-** The Tender Specification can be obtained from & payment towards the cost of Tender papers as mentioned (Non- Refundable) in shape of Demand Draft /Term Deposit to be drawn in favour of Block Development Officer, Bonth in any Nationalized Bank having its branch at Bhadrak on any working day **on or of from 02.11.2024 to 14.11.2024** for the above work.
- 2. Date of receipt and mode of submission of Tender Papers:-** The tender papers have to be submitted as sealed tender papers in complete shape through **Registered Post/ Speed Post** only, directly sending it to the BDO Bonth in his official postal address. The last date of receipt of tender paper is **14.11.2024 upto 1.00 PM**. The undersigned will not be responsible for postal delay if any non-receipt of the tender papers in time. **The bidders must super scribe the name of the work/project on the sealed envelope.**
- 3. Date of Opening of Tender Paper:-**The tender paper shall be opened on **14.11.2024 at 3.00 PM** in the presence of the bidders or in their authorized representative having **written authorization** for the purpose before the tender committee in the conference Hall of Bonth Block Office.
- 4. Documents to be attached:-**The following documents should be furnished with the tender paper failing which the tender will be liable for rejection.
 - (G) Self attested copy of contractor Registration Certificate.
 - (H) Self attested copy of PAN card/Certificate of GSTIN.
 - (I) Demand Draft/Term Deposit Receipt of Paper Cost & EMD.
 - (J) Self attested copy of caste certificate issued by competent authorities in case of SC/ST Contractors desirous of availing preference.
 - (K) The bidders must produce an original affidavit in support of the authenticity of documents attached with the tender papers.
 - (L) Joint venture consortium agreements are not allowed to participate tender.
- 5. Shortfall of any required documents and tender paper is liable for rejection.**


Block Development Officer
Bonth

6. **E.M.D @1%** of tender value shall be pledged in favour of Block Development Officer along with the bids
7. **Additional Performance Security Deposit:-** The affidavit in support of APS will be submitted by the successful bidder for the cost of less quoted in percentage of the amount put to tender before signing of the agreement of the contract.(Vide works Department letter No-16659/W dated-20.09.2022 Govt. of Odisha,Works Department) As per office memorandum No-6559 dated-06.06.2021 of Works Deptt., Govt. of Odisha modification to APS will be followed as detailed below:

SI NO.	Range of Difference between the estimated cost put to tender & Bid amount	Additional performance Security to be deposited by the successful Bidder
1	Below 5%	No additional Performance Security
2	From 5% & above & below 10%	50% of (Difference between estimated cost put to tender & Bid amount)
3	From 10% & above	150% of (Difference between estimated cost put to tender & Bid amount)

8. Submission of more than one tender paper by bidder for a single work will be liable for rejection of all such tender papers.
9. **The Block Development Officer, Bonth reserves the right to reject any or all the tenders without assigning any reason at any stage of bidding process thereof .Other details can be seen in the bidding documents.**
10. If rate quoted by the bidder is less than 15% of the amount put to tender, then such a bid shall be rejected & all the tenders shall be finalized basing of merits of rest bids. But if more than one bid is quoted (decimal upto two numbers will be taken for all practical purposes) either all the estimated cost put to tender or less than the estimated cost put to tender, the tender accepting authority will finalize the tender through a transparent lottery system, where all bidders/ their authorized representative, the concerned SE/Executive Engineer of concerned Division DAO will remain present vide works Deptt O.M No- 1437 dated-31/01/2023
11. **No Tender paper shall be received through Drop Box or Courier Services & tender paper received through Drop Box or Courier Services shall be liable for rejection.**


Block Development Officer
Bonth

Memo No- 3391

Date- 28.10.2024


Copy submitted to the Director, I & PR, Govt. of Odisha, Bhubaneswar for favour of kind information.


28/10/2024
Block Development Officer
Bonth

Memo No- 3392

Date- 28.10.2024

Copy Submitted to The Collector & DM, Bhadrak / CDO-cum-EO, ZP, Bhadrak/ DWO, Bhadrak/ District Planning Officer, Bhadrak /D.I & P.R.O, Bhadrak for favour of kind information & necessary action.


28/10/2024
Block Development Officer
Bonth

Memo No.- 3393

Date- 28.10.2024

Copy forwarded to EE, Bhadrak/ EE, R.W.S & S, Bhadrak, EE R & B Divison, Bhadrak/ EE,M.I. Divison, Bhadrak/EE,R.W Divison, Bhadrak/ All BDOs of Bhadrak District/ Tahasildar, Bonth/ IIC, Bonth, Bonth PS/ CDPO, ICDS, Bonth for information & necessary action with request to display in their Notice board for wide circulation.


28/10/2024
Block Development Officer
Bonth

Memo No- 3394

Date- 28.10.2024

Copy forwarded to The DeGM, Bhadrak for information with a request to upload the detail tender call notice, tender schedule and the bid documents in the official website of Bhadrak i.e <http://bhadrak.odisha.gov.in>


28/10/2024
Block Development Officer
Bonth

Memo No- 3395

Date- 28.10.2024

Copy to Office Notice Board & C.P,Bonth Block to assist for uploading the DTCN & bid documents at NIC, Bhadrak.


28/10/2024
Block Development Officer
Bonth

Annexure-1

BID IDENTIFICATION NUMBER	NAME OF THE WORK	APPROXI. EST COST PUT TO TENDER	CLASS OF CONTRACTOR	EMD(1%)Approx.	COST OF TENDER PAPER	TIME OF COMPLETION
2	3	4	5	6	7	8
PSB-01/2024-25	Const. of Additional Classroom at Kandaba Nodal School, Gopinathpur GP	Rs. 12,07,338	'C' & 'D'	Rs.12,073	Rs.6,000/-	SIX CALENDAR MONTH


28/10/2024
Block Development Officer
Bonth

TENDER SCHEDULE

Name of the work :- Construction of additional Class Room at Kandaba Nodal School at Gopinathpur -GP, Block-Bonth, Dist-Bhadrak

Tender Schedule Cost :- ₹ 12,11,411.00 12,07,338.00

Sl.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
					(Rs.)
Part - A Civil Cost)					
1	Foundation excavation in hard soil including levelling and dressing the bed and sides depositing muck within initial lead and lift etc. complete as per direction of Engg-in-Charge .	14.650	Cum.	269.70	3,951.11
2	Filling foundation and plinth with sand and well watered and rammed including cost, conveyance and royalty etc complete as per direction of Engg.-in-Charge.	28.140	Cum.	1,054.03	29,660.40
3	Cement concrete (1:3:6)with 40mm size CBHG metal including cost, conveyance and royalty etc. complete as per direction of Engg.-in-Charge.	7.630	Cum.	6,418.15	48,970.48
4	Fly Ash Brick masonry in c.m. 1:6 in F & P including cost,conveyance and royalty of materials curing etc. complete. as per the direction of the Engineer-in-charge.	8.500	Cum.	5,821.95	49,486.58
5	1" thick D.P.C with C.C(1:2:4) using 12mm. Chips etc. cpmplete as per direction of Engg-in-Charge .	8.988	Sqm	367.47	3,302.64
6	1st class Fly Ash brick masonry work in superstructure thoroughly soaked in water, with cement mortar (1:6) including scaffoldings ,racking out joints, curing etc complete as per specification/drawing and as per the direction of the Engineer-in-charge.				
	i Ground Floor Floor	14.940	Cum.	5,855.28	87,477.88
7	R.C.C. work M20 grade using 20mm.and down grade HBG crusher broken chips including hoisting,laying, cost,conveyance and royalty of materials curing including centering and shuttering etc. complete as per direction of Engg-in-Charge .				
	i Column Base				
	a Ground Floor	5.500	Cum.	6,958.87	38,273.79
	ii Plinth Beam / Tie Beam				
	a Ground Floor	1.510	Cum.	7,828.90	11,821.64
	iii Beam & Column				

Sl.	DESCRIPTION		QTY	UNIT	RATE	AMOUNT
						(Rs.)
	a	Ground Floor	5.740	Cum.	16,067.84	0,92,229.40
	iv	65mm avg. Chajja				
	a	Ground Floor	10.800	Sqm.	1,239.47	13,386.28
	v	Roof Slab				
	a	Ground Floor	7.350	Cum.	13,962.20	1,02,622.17
	vi	Lintel				
	a	Ground Floor	1.700	Cum.	14,552.56	24,739.35
8		Single under reamed pile foundation with RCC M20 using 25mm and down graded size black hard granite (Crusher broken) stone chips including cost of boring but excluding cost of M.S./Tor steel and labour charges for cutting, bending and binding of steel. etc. complete 300mm pile - 5.00m long	20	Pile	5,191.75	1,03,835.00
9		Supplying, fitting and placing uncoated HYSD bar reinforcement complete in proper position including cost of binding wire 18 to 20 gauge as per direction of Engg.-in-Charge.				
	i	Ground Floor	34.160	Qtl	9,033.94	3,08,599.39
10		12mm cement plaster in cement mortar (1:6)including necessary scaffolding curing etc. as per direction of Engg.-in-Charge.				
	i	Ground Floor	91.530	Sqm	192.47	17,616.78
11		16mm thick cement plaster in cement mortar (1:6) including necessary scaffolding curing etc. as per direction of Engg.-in-Charge.				
	i	Ground Floor	98.800	Sqm	276.08	27,276.70
12		6mm.thick cement plaster with C.M(1:4) to RCC surface including closed deep chipping and slury treatment etc. complete as per direction of Engg.-in-				
	i	Ground Floor	75.170	Sqm	212.15	15,947.32
13		Fixing Vitrified tiles in floors of size 600mm x600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar (1:4)and filling joints with white cement of approved quality including cost of all materials, labour T&P etc rrequired for the work all completeas per direction of Engineer-in-charge.				
	i	Ground Floor	47.860	Sqm	1,141.75	54,644.16

Sl.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
					(Rs.)
14	Fixing Vitrified tiles in dados skirting and risers of stepson 12 mm thick cement plaster(1:3) jointed with neat cement slurry mixed with pigments to matche shade of the tiles including rubbing and polishing complete as per direction of Engineer-in-charge.				
	i Ground Floor	5.200	Sqm	1,300.35	6,761.82
15.	Wall Priming one coats on new work with wall water bound primer of approved shade as per direction of Engg-in-Charge .				
	i Ground Floor	260.300	Sqm	76.49	19,910.35
16.	Wall painting two coats on new work with Plastic Emulsion Paint of approved shade etc. complete as per direction of Engg-in-Charge .				
	i Ground Floor	143.870	Sqm	107.28	15,434.37
17.	Finishing wall surface of walls with Acrylic wall putty (Water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes, labour T & P etc. complete as per direction of Engg-in-Charge .				
	i Ground Floor	143.870	Sqm	89.60	12,890.75
18.	Wall painting two coats on new work with Weather coat paint of approved shade as per direction of Engg.-in-Charge.				
	i Ground Floor	116.430	Sqm	96.92	11,283.81
19.	Supplying ,fitting and fixing of MS steel shutter with frame with MS angle frame of 35x35x6mm and shutter section of 30x30x5mm MS angle with welding of 25x6mm flat and welding of 16 gauge CR sheet witharrangement of clamp, fitting of 3 nos of 4" hinges and 300mm x16 mm MS aldrop with 8" Tower bolt including cost, conveyance, and taxes of all materials, labour , T&P etc required for complete in all respect.				
	(i) All Floors	478.080	Kg.	99.30	47,473.34
20	Emel Painting two coats with enamel paint over one coat of primer of approved quality etc. complete as per direction of Engg-in-Charge .				
	i Ground Floor	29.160	Sqm	259.78	7,575.18
21	20mm. thick grading plaster in c.m. 1:4 over roof slab and chujja including cost conveyance and royalty of materials curing etc. complete as per direction of Engg-in-Charge .				
	i Ground Floor	58.870	Sqm	301.37	17,741.36

Sl.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
					(Rs.)
22	Supplying,fitting & fixing of stainless steel of 304 grade in Hand Railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm.x2mm. @ 0.90m. C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification,buffering,polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect etc. complete as per direction of Engg-in-Charge .	6.500	Mt.	3,588.31	23,324.02
23	Fixing industrial Chequered tiles in floors,treads or steps and landings on 25 mm thick CM (1:1) jointed with neat cement slurry mixed with pigments to match the shades includind cost for rubbing, polishing & cost of tiles etc. complete as per direction of Engg-in-Charge .				
	(i) Ground Floor	11.340	Sqm.	979.02	11,102.09
G. Total					12,07,338.00

Approved 23 items only (Rupees twelve lakhs ^{seven} ~~eleven~~ thousand four ^{thirty} ~~four~~ hundred ^{eight} ~~eleven~~ only)


30.7.24
Junior Engineer
Bonth Block


30.07.2024
Asst. Executive Engineer
Assistant Exe. Engineer
Bonth Block


Block Development Officer
Bonth Block

My / our quoted rate is _____ % (both in figure and words) excess over / less than / equal to the above estimated cost.

NOTES:


1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:


Addl. Executive Officer (Tech.)
Zilla Parishad, Bhadrak