

# OFFICE OF THE PANCHAYAT SAMITI, BONTH

At/PO- Bonth, Dist- Bhadrak, PIN- 756114

E-mail id- [ori-bonth@nic.in](mailto:ori-bonth@nic.in)

Letter no.889

Date-25.03.2026

## DETAILED TENDER CALL NOTICE 01/BDO,BONTH OF 2026-27

The Block Development Officer, Bonth invites a sealed percentage rate tender in single cover system on behalf of Governor of Odisha from registered & eligible class of Civil contractor of the state P W D (R&B) / Water resource / Rural Works / M.I/C.P.W.D for the following works. **The Block Development Officer, Bonth reserves the right to reject any or all the tenders without assigning any reason thereof.** Other details can be seen in Annexure-1.

### Term & Condition

- 1. Cost of Tender Paper :-** The Tender Specification can be obtained from & payment towards the cost of Tender papers as mentioned ( Non- Refundable) in shape of Demand Draft /Term Deposit to be drawn in favour of Block Development Officer, Bonth in any Nationalized Bank having its branch at Bhadrak on any working day **on or of from 02.04.2026 to 16.04.2026** for the above work.
- 2. Date of receipt and mode of submission of Tender Papers:-** The tender papers have to be submitted as sealed tender papers in complete shape through **Registered Post/ Speed Post** only, directly sending it to the BDO Bonth in his official postal address. The last date of receipt of tender paper is **16.04.2026 upto 1.00 PM**. The undersigned will not be responsible for postal delay if any non-receipt of the tender papers in time. **The bidders must super scribe the name of the work/project on the sealed envelope.**
- 3. Date of Opening of Tender Paper:-**The tender paper shall be opened on **17.04.2026 at 11.00 AM** in the presence of the bidders or in their authorized representative having **written authorization** for the purpose before the tender committee in the conference Hall of Bonth Block Office.
- 4. Documents to be attached:-**The following documents should be furnished with the tender paper failing which the tender will be liable for rejection.
  - (A) Self attested copy of contractor Registration Certificate.
  - (B) Self attested copy of PAN card/Certificate of GSTIN.
  - (C) Demand Draft/Term Deposit Receipt of Paper Cost & EMD.
  - (D) Self attested copy of caste certificate issued by competent authorities in case of SC/ST Contractors desirous of availing preference.
  - (E) The bidders must produce an original affidavit in support of the authenticity of documents attached with the tender papers.
  - (F) Joint venture consortium agreements are not allowed to participate tender.
- 5. Shortfall of any required documents and tender paper is liable for rejection.**

  
Block Development Officer  
Bonth

6. **E.M.D @1%** of tender value shall be pledged in favour of Block Development Officer along with the bids
7. **Additional Performance Security** (As per Works Department OM No.173 dt.03.01.2026) shall be obtained from the bidder when the bid amount is less than estimated cost put to the tender. In such an event, only the successful bidder who has quoted less bid price / rates than the estimated cost put to tender shall have to furnish the Additional Performance Security as per the following rate. Additional performance security shall be taken on an incremental basis from the selected bidder for low bid prices in the project works as under.
- (I) **Where the bid price is below 0% but not below 10% of the project cost put to bid,** no additional performance guarantee/security percentage is required.
- (II) **Where the bid price is below 10% but not below 20% of the project cost put to bid,** the additional performance guarantee/security percentage shall be incremented by 0.1% for every percentage of bid price below 10% of the project cost put to bid starting at 11% with the additional bid performance guarantee being 0.1% and this additional performance guarantee percentage shall be applied on the bid price.
- (III) **Where the bid price is 20% or more below of the project cost put to bid,** the additional performance guarantee percentage shall be incremented by 0.2% for every percentage of bid price below 20% of the project cost put to bid in addition to 1% of the bid price and this additional performance guarantee percentage shall be applied on the bid price.
- (IV) The additional performance guarantee percentage shall be rounded off to the next lower percentage based on whether the decimal point of the percentage of bid price is below 0.5% or next higher percentage based on whether the decimal point of the percentage of bid price is 0.5% or more.
- (V) The additional performance security shall be treated as part of the performance security.
- (VI) Justification for abnormally low bids shall be scrutinized by the Departmental Technical Committee and recommended to the competent authority of the Administrative Department for the approval of the Additional Performance Security (APS). An abnormally low bid is one in which the Bid price, in combination with other elements of the Bid, appears so low that it raises material concerns as to the capability of the Bidder to perform the contract at the offered price. Procuring Entity may, in such cases, seek written clarifications from the Bidder, including detailed price analyses of its Bid price in relation to scope, schedule, resource mobilization, allocation of risks and responsibilities, and any other requirements of the bid document. If, after evaluating the price analyses, the procuring entity determines that the Bidder has substantially failed to demonstrate its capability to deliver the contract at the offered price, the Procuring Entity may reject the Bid/Proposal.

*SKB*

However, it would not be advisable to fix a normative percentage below the estimated cost, which would automatically be considered as an abnormally low bid.

If more than one bid is quoted (decimal up to two numbers will be taken for all practical purposes), either at the estimated cost put to tender or less than the estimated cost put to tender, the tender accepting Authority will finalize the tender through a transparent lottery system, where all the concerned bidders/their authorized representatives, the concerned BDO will remain present.

If the rate quoted by the SC and ST Category Contractors comes to the rate quoted by the L1 bidder (decimal up to two numbers will be taken for all practical purposes) after availing 10% price preference as per Para 2 of Works Department Resolution No.27748 dated 11.10.1977, the tender shall be finalized by the tender accepting authority through a transparent lottery system along with other categories of contractors.

**The Additional Performance Security (APS) shall be in shape of TDR/BG of any Nationalized/ Scheduled Bank duly pledged in favour of the BDO, Bonth within seven days of issue of Letter of Acceptance (LoA) by the BDO,PS Bonth to the successful bidder otherwise the bid of the successful bidder shall be cancelled. Further proceeding for blacklisting shall be initiated against the bidder. If the APS is submitted in shape of Bank Guarantee by the bidder. then the validity of the Bank Guarantee should be for a minimum period equal to the period allowed for completion of the work plus defect liability period of one year and one month extra for transaction period.**

8. Submission of more than one tender paper by bidder for a single work will be liable for rejection of all such tender papers.
9. Validity of tender shall be a period of 90 (ninety) days from the last date of receipt of bids. If any bidder/tenderer withdraw his bid or tender before the said period or make any modification in terms and conditions of the bid, the EMD deposited at the time of submission of the tender shall stands forfeited.
10. The contractor has to quote the percentage excess or less upto two digits only after decimal point. If he quotes the percentage excess or less in more than two digits after decimal points the first two digits after decimal point shall only be considered without rounding off.
11. In the eventually of failure on the part of lowest successful bidder to produce the original documents, he or she shall be debarred in future from participating in tender for 3 years and action will be initiated for blacklisting by the competent authority.
12. **The Block Development Officer, Bonth reserves the right to reject any or all the tenders without assigning any reason thereof .Other details can be seen in the bidding documents.**

Memo No:-890

Date-25.03.2026

Copy submitted to the Director, I & PR, Govt. of Odisha, Bhubaneswar for favour of kind information.

  
Block Development Officer  
Bonth

Memo No:-891

Date-25.03.2026

Copy Submitted to The Collector & DM, Bhadrak / CDO-cum-EO, ZP, Bhadrak/ DWO, Bhadrak/ District Planning Officer, Bhadrak /D.I & P.R.O, Bhadrak for favour of kind information & necessary action.

  
Block Development Officer  
Bonth

Memo No:- 892

Date-25.03.2026

Copy forwarded to EE, Bhadrak/ EE, R.W.S & S, Bhadrak, EE R & B Divison, Bhadrak/ EE,M.I. Divison, Bhadrak/EE,R.W Divison, Bhadrak/ All BDOs of Bhadrak District/ Tahasildar, Bonth/ IIC, Bonth, Bonth PS/ CDPO, ICDS, Bonth for information & necessary action with request to display in their Notice board for wide circulation.

  
Block Development Officer  
Bonth

Memo No:-893

Date-25.03.2026

Copy forwarded to The DeGM, Bhadrak for information with a request to upload the detail tender call notice, tender schedule and the bid documents in the official website of Bhadrak i.e <http://bhadrak.odisha.gov.in>

  
Block Development Officer  
Bonth

Memo No:-894

Date-25.03.2026

Copy to Office Notice Board & C.P,Bonth Block to assist for uploading the DTCN & bid documents at NIC, Bhadrak.

  
Block Development Officer  
Bonth

## Annexure-1

BID IDENTIFICATION NUMBER	NAME OF THE WORK	APPROX. EST COST PUT TO TENDER	CLASS OF CONTRACTOR	EMD(1%) Approx.	COST OF TENDER PAPER	TIME OF COMPLETION
2	3	4	5	6	7	8
PSB-01/2025-26	Const. of Additional Classroom at Satyanarayan Nodal UP school, Dando, Kenduapada GP	Rs. 13,35,777	'C' & 'D'	Rs.13,400	Rs.6,000/-	SIX CALENDAR MONTH
PSB-02/2025-26	Const. of Additional Classroom at Gopinathjew High School, Gopinathpur GP	Rs. 16,79,487	'C' & 'D'	Rs.16,800	Rs.6,000/-	SIX CALENDAR MONTH
PSB-03/2025-26	Const. of Bio medical waste management at Bonth	Rs. 6,00,739	'C' & 'D'	Rs.6,000	Rs.4,000/-	FOUR CALENDAR MONTH

*Sue*

**Block Development Officer**  
**Block Development Officer**  
**Bonth**  
**Bonth**

## TENDER SCHEDULE

Name of the work :- **CONSTRUCTION OF BIO MEDICAL WASTE MANAGEMENT OF BONTH BLOCK, DIST. BHADRAK.**

Tender Schedule Cost :- ₹ 6,00,739.00

SI.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
					(Rs.)
<b>Part - A Civil Cost)</b>					
1	Foundation excavation in hard soil including levelling and dressing the bed and sides depositing muck within initial lead and lift etc. complete as per direction of Engg-in-Charge .	2.126	Cum.	274.15	583.00
2	Filling foundation and plinth with sand and well watered and rammed including cost, conveyance and royalty etc complete as per direction of Engg.	10.349	Cum.	1,318.50	13,645.00
3	Cement concrete (1:3:6)with 40mm size CBHG metal including cost, conveyance and royalty etc. complete as per direction of Engg.-in-Charge.	3.078	Cum.	6,891.75	21,216.00
4	1st class Fly Ash brick masonry work in superstructure thoroughly soaked in water, with cement mortar (1:6) including scaffoldings ,racking out joints, curing etc complete as per specification/drawing and as per the direction of the Engineer-in-charge.	17.138		6,559.14	1,12,410.00
5	R.C.C. work M20 grade using 20mm.and down grade HBG crusher broken chips including hoisting,laying, cost,conveyance and royalty of materials curing including centering and shuttering etc. complete as per direction of Engg-				
	i <b>Pile cap</b>				
	a Ground Floor	2.293	Cum.	7,288.26	16,710.00
	ii <b>Plinth Beam / Tie Beam</b>				
	a Ground Floor	2.302	Cum.	7,184.52	16,541.00
	iii <b>Beam &amp; Column</b>				
	a Ground Floor	1.151	Cum.	16,030.30	18,453.00
	b Column	1.404	Cum.	16,030.30	22,505.00
	iv <b>65mm avg. Chajja</b>				
	a Ground Floor	0.000	Sqm.	7,090.83	-
	v <b>Roof Slab</b>				
	a Ground Floor	3.923	Cum.	13,690.78	53,709.00


*Sa*  
Block Development Officer  
BONTH


*K. Lath*  
19.08.2022  
Asst. Executive Engineer  
Bonth Block

*D. D. D. D.*  
19/8/22  
BONTH BLOCK

DESCRIPTION		QTY	UNIT	RATE	AMOUNT
					(Rs.)
vi	Lintel				
a	Ground Floor	1.151	Cum.	14,724.20	16,950.00
6	Single under reamed pile foundation with RCC M20 using 25mm and down graded size black hard granite (Crusher broken) stone chips including cost of boring but excluding cost of M.S./Tor steel and labour charges for cutting, bending and binding of steel. e	12	Pile	3,647.08	43,765.00
7	Supplying, fitting and placing uncoated HYSD bar reinforcement complete in proper position including cost of binding wire 18 to 20 gauge as per direction of Engg.-in-Charge.				
i	Ground Floor	16.500	Qtl	9,580.26	1,58,074.00
8	12mm cement plaster in cement mortar (1:6) including necessary scaffolding curing etc. as per direction of Engg.-in-Charge.				
i	Ground Floor	92.558	Sqm	176.70	16,355.00
9	16mm thick cement plaster in cement mortar (1:6) including necessary scaffolding curing etc. as per direction of Engg.-in-Charge.				
i	Ground Floor	106.970	Sqm	256.33	27,420.00
10	6mm.thick cement plaster with C.M(1:4) to RCC surface including closed deep chipping and slurry treatment etc. complete as per direction of Engg.-in-Charge.				
i	Ground Floor	18.216	Sqm	214.60	3,909.00
11	2.5 CM Thick A.S Flooring	25.325	Sqm	436.24	11,048.00
12.	Wall Priming one coats on new work with wall water bound primer of approved shade as per direction of Engg-in-Charge .				
i	Ground Floor	110.773	Sqm	80.47	8,914.00
13.	Wall painting two coats on new work with Plastic Emulsion Paint of approved shade etc. complete as per direction of Engg-in-Charge .				
i	Ground Floor	125.186	Sqm	108.92	13,635.00
14.	Wall painting two coats on new work with Weather coat paint of approved shade as per direction of Engg.-in-Charge.				
i	Ground Floor	92.558	Sqm	98.51	9,118.00

  
Block Development Officer  
BONTH

  
19.03.2022  
Asst. Executive Engineer  
Block

  
A.E.  
BONTH

DESCRIPTION	QTY	UNIT	RATE	AMOUNT
				(Rs.)
5 Enamel Painting two coats with enamel paint over one coat of primer of approved quality etc. complete as per direction of Engg-in-Charge .				
i Ground Floor	24.566	Sqm	336.05	8,255.00
16 20mm. thick grading plaster in c.m. 1:4 over roof slab and chujja including cost conveyance and royalty of materials curing etc. complete as per direction of Engg-in-Charge .				
i Ground Floor	28.248	Sqm	266.34	7,524.00
<b>G. Total</b>				<b>6 ,00 ,739.00</b>

Approved 16 (Sixteen ) items only (Rupees Six lakhs Sixty four thousand Seven hundred Ten ) only

*D. Sachin*  
19/3/26  
**A.E.**  
**BONTH BLOCK**  
Asst. Engineer  
Bonth Block

*Clary*  
19.03.2026  
**Asst. Executive Engineer**  
**Bonth Block**  
Asst. Executive Engineer  
Bonth Block

*S. K. S.*  
**Block Development Officer**  
Block Development Officer  
Bonth Block

My / our quoted rate is \_\_\_\_\_ % (both in figure and words) excess over / less than / equal to the above estimated cost.

**NOTES:**

- The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
- Strike out which is not applicable.
- Percentage should be quoted up to 2 (two) digits after the decimal point.
- Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer  
No. of Correction: .....

No. of over writing: .....

No. of interpolation: .....


## TENDER SCHEDULE

me of the work :- **CONSTRUCTION OF ADDITIONAL CLASS ROOM AT- SATYANARAYAN NODAL UP SCHOOL, VILL.. DANDO,G.P.**

nder Schedule Cost :- ₹ 1,335,777.00

DESCRIPTION	QTY	UNIT	RATE	AMOUNT
				(Rs.)
<b>Part - A Civil Cost)</b>				
Foundation excavation in hard soil including levelling and dressing the bed and sides depositing muck within initial lead and lift etc. complete as per direction of Engg-in-Charge .	8.230	Cum.	206.05	1,696.00
Filling foundation and plinth with sand and well watered and rammed including cost, conveyance and royalty etc complete as per direction of Engg.-	54.250	Cum.	1,019.31	55,298.00
Cement concrete (1:3:6)with 40mm size CBHG metal including cost, conveyance and royalty etc. complete as per direction of Engg.-in-Charge.	9.430	Cum.	6,588.41	62,129.00
Fly Ash Brick masonry in c.m. 1:6 in F & P including cost,conveyance and royalty of materials curing etc. complete. as per the direction of the Engineer-in-charge.	8.490	Cum.	5,836.05	49,548.00
1" thick D.P.C with C.C(1:2:4) using 12mm. Chips etc. cpmplete as per direction of Engg-in-Charge .	11.720	Sqm	376.56	4,413.00
1st class Fly Ash brick masonry work in superstructure thoroughly soaked in water, with cement mortar (1:6) including scaffoldings ,racking out joints, curing etc complete as per specification/drawing and as per the direction of the Engineer-in-charge.				
i Ground Floor Floor	17.420	Cum.	5,869.38	102,245.00
ii First Floor (Head Room) & Parapet	0.000	Cum.	6,224.53	-
R.C.C. work M20 grade using 20mm.and down grade HBG crusher broken chips including hoisting,laying, cost,conveyance and royalty of materials curing including centering and shuttering etc. complete as per direction of Engg-				
i Column Base				
a Ground Floor	5.950	Cum.	7,075.18	42,097.00
ii Plinth Beam / Tie Beam				
a Ground Floor	2.290	Cum.	7,950.08	18,206.00
iii Beam & Column				

  
Block Development Officer  
BONTH

  
Asst. Engr. 19.03.2021  
Bonth Block

  
19.03.21  
BONTH BLOCK  
Bonth Block

DESCRIPTION		QTY	UNIT	RATE	AMOUNT
					(Rs.)
a	Ground Floor	6.070	Cum.	16,328.07	0,99,111.00
b	First Floor (Head Room)	0.000	Cum.	18,409.57	-
iv	65mm avg. Chajja				
a	Ground Floor	0.710	Sqm.	1,256.26	892.00
v	Roof Slab				
a	Ground Floor	8.630	Cum.	14,161.63	1,22,215.00
vi	Lintel				
a	Ground Floor	1.820	Cum.	14,729.37	26,807.00
	Single under reamed pile foundation with RCC M20 using 25mm and down graded size black hard granite (Crusher broken) stone chips including cost of boring but excluding cost of M.S./Tor steel and labour charges for cutting, bending and binding of steel. e	22	Pile	5,264.06	1,15,809.00
	Supplying, fitting and placing uncoated HYSD bar reinforcement complete in proper position including cost of binding wire 18 to 20 gauge as per direction of Engg.-in-Charge.				
i	Ground Floor	35.143	Qtl	8,315.49	2,92,231.00
ii	First Floor (Head Room)	0.000	Qtl	9,066.57	-
	12mm cement plaster in cement mortar (1:6) including necessary scaffolding curing etc. as per direction of Engg.-in-Charge.				
i	Ground Floor	147.825	Sqm	193.60	28,619.00
ii	First Floor (Head Room)	0.000	Sqm	200.08	-
	16mm thick cement plaster in cement mortar (1:6) including necessary scaffolding curing etc. as per direction of Engg.-in-Charge.				
i	Ground Floor	86.337	Sqm	278.65	24,058.00
	6mm.thick cement plaster with C.M(1:4) to RCC surface including closed deep chipping and slury treatment etc. complete as per direction of Engg.-in-Charge.				
i	Ground Floor	89.650	Sqm	214.19	19,202.00

*SG*

Block Development Officer  
BONTH

*Clashy*  
19.03.2026

Asst. Executive Engineer  
Benth Block

*19.3.26*  
A.A.E.  
BONTH BLOCK  
BONTH

DESCRIPTION	QTY	UNIT	RATE	AMOUNT
				(Rs.)
Fixing Vitrified tiles in floors of size 600mm x600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar (1:4)and filling joints with white cement of approved quality including cost of all materials, labour T&P etc rrequired for th				
i Ground Floor	55.576	Sqm	1,141.23	63,425.00
Fixing Vitrified tiles in dados skirting and risers of stepson 12 mm thick cement plaster(1:3) jointed with neat cement slurry mixed with pigments to matche shade of the tiles including rubbing and polishing complete as per direction of Engineer-in-cha				
i Ground Floor	5.374	Sqm	1,751.56	9,413.00
Wall Priming one coats on new work with wall water bound primer of approved shade as per direction of Engg-in-Charge .				
i Ground Floor	323.813	Sqm	77.88	25,219.00
ii First Floor (Head Room)	0.000	Sqm	77.22	-
Wall painting two coats on new work with Plastic Emulsion Paint of approved shade etc. complete as per direction of Engg-in-Charge .				
i Ground Floor	175.987	Sqm	108.92	19,169.00
Finishing wall surface of walls with Acrylic wall putty (Water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes, labour T & P etc. complete as p				
i Ground Floor	175.987	Sqm	91.09	16,031.00
Wall painting two coats on new work with Weather coat paint of approved shade as per direction of Engg.-in-Charge.				
i Ground Floor	147.825	Sqm	98.51	14,562.00
ii First Floor (Head Room)	0.000	Sqm	98.97	-
Supplying ,fitting and fixing of MS steel shutter with frame with MS angle frame of 35x35x6mm and shutter section of 30x30x5mm MS angle with welding of 25x6mm flat and welding of 16 gauge CR sheet witharrangement of clamp, fitting of 3 nos of 4" hinges				

Block Development Officer  
BONTH

*A. Lath*  
19.03.2026  
Asst. Executive Engineer  
Benth Block

*B*  
19.3.26  
BONTH BLOCK  
Benth Block

DESCRIPTION		QTY	UNIT	RATE	AMOUNT
					(Rs.)
(i)	All Floors	376.000	Kg.	105.51	39,672.00
Enamel Painting two coats with enamel paint over one coat of primer of approved quality etc. complete as per direction of Engg-in-Charge .					
i	Ground Floor	20.446	Sqm	255.87	5,232.00
20mm. thick grading plaster in c.m. 1:4 over roof slab and chujja including cost conveyance and royalty of materials curing etc. complete as per direction of Engg-in-Charge .					
i	Ground Floor	68.122	Sqm	301.36	20,529.00
Fixing industrial Chequered tiles in floors,treads or steps and landings on 25 mm thick CM (1:1) jointed with neat cement slurry mixed with pigments to match the shades includind cost for rubbing, polishing & cost of tiles etc. complete as per direction					
(i)	Ground Floor	16.793	Sqm.	1,309.48	21,990.00
Supplying,fitting & fixing of stainless steel of 304 grade in Hand Railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm.x2mm. @ 0.90m. C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case					
<b>G. Total</b>					<b>13,35,777.00</b>

**Approved 23 (twentythree) items only (Rupees thirteen lakhs thirty five thousand seven hundred seventy seven) only**

*14.3.26*  
Asst. Engineer  
BONTH BLOCK  
Bonth Block

*19.03.2022*  
Assistant Exe. Engineer  
Asst. Executive Engineer  
Bonth Block  
Bonth Block

*SUP*  
Block Development Officer  
BONTH  
Bonth Block

My / our quoted rate is \_\_\_\_\_ % (both figure and words) excess over / less than / equal to the above estimated cost.

**NOTES:**

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.

## TENDER SCHEDULE

**Abstract of cost for Construction of ACR at Gopinath Jew High School,  
Vill-Gopinathpur, G.P-Gopinathpur, Black-Banth, Dist-Bhadrak**

**Tender Schedule Cost :- ₹ 1,679,487.00**

Sl.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
					(Rs.)
<b>PART-A ( CIVIL )</b>					
1	Foundation excavation in ordinary soil soil including levelling and dressing the bed and sides depositing muck within initial lead and lift etc. complete as per direction of Engg-in-Charge .	27.140	Cum.	206.05	5,592.20
2	Filling foundation and plinth with sand and well watered and rammed including cost, conveyance and royalty etc complete as per direction of Engg.-in-Charge.	101.930	Cum.	1,124.51	114,621.30
3	Levelling Course for Pile cap Providing and laying of PCC M15 levelling course 100mm thick below the pile cap. including hoisting, laying, cost, conveyance and royalty of materials curing etc. complete as per direction of Engg-in-Charge . As per AR-2006, Apge No.-263, item No.-5	5.130	Cum.	6,157.55	31,588.23
4	Fly Ash Brick masonry in c.m. 1:6 in F & P including cost, conveyance and royalty of materials curing etc. complete. as per the direction of the Engineer-in-charge.	9.900	Cum.	5,865.50	58,068.45
5	Providing and Laying reinforcement Cement concrete (M-20) with 20 mm and down graded chips including cost all materials, labours, T & P, curing etc complete (excluding the cost of reinforcement & Centering, shuttering) as per direction of Engineer-in-charge.				
	i Column Footing / Pile Cap	34.090	Cum.	7,080.74	241,382.43
	ii Plinth Beam	10.830	Cum.	7,955.64	86,159.58
	iii Beam & Column (Ground Floor)	6.620	Cum.	16,333.63	1,08,128.63

*G. Lash*  
19.09.2022  
Asst. Executive Engineer  
Banth Block  
Block Development Officer  
Banth

19.9.26  
BOD  
Banth Block

*[Signature]*  
15/3/22  
Addl. Executive Officer (Tech.)  
Zilla Parishad, Bhadrak

6	Single under reamed pile foundation with RCC M20 using 25mm and down graded size black hard granite (Crusher broken) stone chips including cost of boring but excluding cost of M.S./Tor steel and labour charges for cutting, bending and binding of steel. etc. complete 300mm pile - 6.00m long	61	Pile	6,066.19	3,70,037.30
7	Supplying, fitting and placing uncoated HYSD bar reinforcement complete in proper position including cost of binding wire 18 to 20 gauge as per direction of Engg.-in-Charge.				
(i)	Ground Floor	79.840	Qtl	8,315.49	6,63,908.72
<b>Subtotal (A)</b>				<b>Rs.</b>	<b>16,79,480.00</b>

Approved 7 (seven) items only (Rupees Sixteen lakhs seventy nine thousand four hundred eighty seven) only

Asst. Engineer  
Bonth Block

Asst. Executive Engineer  
Bonth Block

Block Development Officer  
Bonth Block

My / our quoted rate is \_\_\_\_\_  
% (both in figure and words) excess over / less than / equal to the above estimated cost.

**NOTES:**

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction: .....

No. of over writing: .....

No. of interpolation: .....

*P. P. Ghosh*

Block Development Officer  
Bonth

Addl. Executive Officer(Tech.)  
Zilla Parishad, Bhadrak