

OFFICE OF THE PANCHYAT SAMITI, DHAMNAGAR

At/Po-Dhamnagar, Dist- Bhadrak, e-mail – ori-dhamnagar@nic.in

Letter No...3067...../ Date...30.06.2026...../

Tender for Construction of Grama Panchayat Level Federation (GPLF) Building & Additional Class Room Building

1. Name of the Work :-

- i) Construction of GPLF Building at Anandapur
- ii) Construction of GPLF Building at Bamkura
- iii) Construction of GPLF Building at Hasanabad
- iv) Construction of GPLF Building at Nadigaon
- v) Construction of GPLF Building at Karada
- vi) Construction of GPLF Building at Khadipada
- vii) Construction of Additional Class Room at Indragobinda Nodal High School, GP- Daipur
- viii) Construction of Additional Class Room at Khangara Nodal UPS, GP- Karada.
- xi) Construction of Additional Class Room at Dhamnagar Feeder Primary School, Dhamnagar NAC.
- x) Construction of Additional Class Room at Sahaspur Nodal UPS GP- Sahaspur

2. Total No. of Work :- 10 No.s
3. Approximate Estimated Cost :- As per DTCN
4. Class Contractor :- "B & C" for GPLF Building & "C & D" for ACR
5. Period of Completion :-Six Calendar Months
6. Other Details :-The Details are as follows

Sl. No.	Bid Identification No.	Available Tender-On- line for bidding		Last date for receipt of Bids	Date & Time of Opening of Bid
		From	TO		
	PSD-01/2025-26 to PSD-10/2025-26	02.07.2026 1.30 PM	09.07.2026 5.00 PM	09.07.2026 5.00 PM	10.07.2026 11.00 AM

7. Further details can be seen from the website portal <http://bhadrak.odisha.gov.in>

8. Any other changes/ Corrigendum/Addendum may be seen only in website <http://bhadrak.odisha.gov.in>


Block Development Officer
Dhamnagar

Memo No. 3068 date- 30.06.2026

Copy forwarded to the Manager (Publication) 1 & PR Department, Government of Odisha, Bhubaneswar with a request to get it published in 2(two) No's of leading Odia daily & 1 (one) no of Local English daily Newspaper at an early date for wide circulation. The Complementary Copy of the newspaper containing the Tender call notice may be sent to this office for reference & record.


Block Development Officer
Dhamnagar

OFFICE OF THE PANCHAYAT SAMITI, DHAMNAGAR

At/Po-Dhamnagar, Dist- Bhadrak, e-mail – ori-dhamnagar@nic.in

Letter No.....3069...../ Date:- 30.06.2026./

DETAIL TENDER CALL NOTICE 01 /BDO, DHAMNAGAR OF 2025-26

The Block Development Officer, Dhamnagar invites a sealed percentage rate tender in single cover system on behalf of Governor of Odisha from registered & eligible class of Civil contractor of the state PWD (R&B) Water resource/ Rural Works/MI/CP.W.D for the following works. The Block Development Officer, Dhamnagar reserves the right to reject any or all the tenders without assigning any reason thereof. Other details can be seen in Annexure-1.

Term & Condition

1. Cost of Tender Paper :- The Tender Specification can be obtained from www.bhadrak.nic.in & payment towards the cost of Tender papers as mentioned (Non-Refundable) in shape of Demand Draft Term Deposit to be drawn in favour of Block Development Officer, Dhamnagar in any Nationalized Bank having its branch at Bhadrak on any working day on or from **02.07.2026 to 09.07.2026** for the above work.

2. Date of receipt and mode of submission of Tender Papers:- The tender papers have to be submitted as sealed tender papers in complete shape through Registered Post/ Speed Post only, directly sending it the BDO Dhamnagar in his official postal address. The last date of receipt of tender paper is **09.07.2026 upto 5.00 PM**. The undersigned will not be responsible for postal delay if any non-receipt of the tender papers in time. The bidders must super scribe the name of the work project on the sealed envelope.

3. Date of Opening of Tender Paper:-The tender paper shall be opened on **10.07.2026 at 11.00 AM** in the presence of the bidders or in their authorized representative having written authorization for the purpose before the tender committee in the Conference Hall of Dhamnagar Block Office

4. Documents to be attached: -The following documents should be furnished with the tender paper failing which the tender will be liable for rejection.

(A) Self attested copy of contractor Registration Certificate.

(B) Self attested copy of PAN card/Certificate of GSTIN

(C) Demand Draft Term Deposit Receipt of Paper Cost & EMD.

(D) Self attested copy of caste certificate issued by competent authorities in case of SC/ST Contractors desirous of availing preference.

(E) The bidders must produce an original affidavit in support of the authenticity of documents attached with the tender papers.

(F) Joint venture consortium agreements are not allowed to participate tender.

5. Shortfall of any required documents and tender paper is liable for rejection.

6. E.M.D 1% of tender value shall be pledged in favour of Block Development Officer, Dhamnagar along with the bids.

7. Additional Performance Security (As per Works Department OM No.173 dt.03.01.2026) shall be obtained from the bidder when the bid amount is less than estimated cost put to the tender. In such an event, only the successful bidder who has quoted less bid price / rates than the estimated cost put to tender shall have to furnish the Additional Performance Security as per the following rate. Additional performance security shall be taken on an incremental basis from the selected bidder for low bid prices in the project works as under.

Sl. No.	Range of Difference between the estimated cost put to tender & Bid amount	Additional performance Security to be deposited by the successful Bidder
1	Below 5%	No additional Performance Security
2	From 5% & above & below 10%	50% of (Difference between estimated cost put to tender & Bid amount)
3	From 10% & above	50% of (Difference between estimated cost put to tender & Bid amount)

(I) **Where the bid price is above 0% but not below 10% of the project cost put to bid,** no additional performance guarantee/security percentage is required.

(II) **Where the bid price is above 10% but not below 20% of the project cost put to bid,** the additional performance guarantee/security percentage shall be incremented by 0.1% for every percentage of bid price below 10% of the project cost put to bid starting at 11% with the additional bid performance guarantee being 0.1% and this additional performance guarantee percentage shall be applied on the bid price.

(III) **Where the bid price is 20% or more below of the project cost put to bid,** the additional performance guarantee percentage shall be incremented by 0.2% for every percentage of bid price below 20% of the project cost put to bid in addition to 1% of the bid price and this additional performance guarantee percentage shall be applied on the bid price.

(IV) The additional performance guarantee percentage shall be rounded off to the next lower percentage based on whether the decimal point of the percentage of bid price is below 0.5% or next higher percentage based on whether the decimal point of the percentage of bid price is 0.5% or more.

(V) The additional performance security shall be treated as part of the performance security.

(VI) Justification for abnormally low bids shall be scrutinized by the Departmental Technical Committee and recommended to the competent authority of the Administrative Department for the approval of the Additional Performance Security (APS). An abnormally low bid is one in which the Bid price, in combination with other elements of the Bid, appears so low that it raises material concerns as to the capability of the Bidder to perform the contract at the offered price. Procuring Entity may, in such cases, seek written clarifications from the Bidder, including detailed price analyses of its Bid price in relation to scope, schedule, resource mobilization, allocation of risks and responsibilities, and any other requirements of the bid document. If, after evaluating the price analyses, the procuring entity determines that the Bidder has substantially failed to demonstrate its capability to deliver the contract at the offered price, the Procuring Entity may reject the

Bid/Proposal. However, it would not be advisable to fix a normative percentage below the estimated cost, which would automatically be considered as an abnormally low bid.

If more than one bid is quoted (decimal up to two numbers will be taken for all practical purposes), either at the estimated cost put to tender or less than the estimated cost put to tender, the tender accepting Authority will finalize the tender through a transparent lottery system, where all the concerned bidders/their authorized representatives, the concerned BDO will remain present.

If the rate quoted by the SC and ST Category Contractors comes to the rate quoted by the L1 bidder (decimal up to two numbers will be taken for all practical purposes) after availing 10% price preference as per Para 2 of Works Department Resolution No.27748 dated 11.10.1977, the tender shall be finalized by the tender accepting authority through a transparent lottery system along with other categories of contractors.

The Additional Performance Security (APS) shall be in shape of TDR/BG of any Nationalized/ Scheduled Bank duly **pledged in favour of the BDO, Dhamnagar** within **seven days** of issue of Letter of Acceptance (LoA) by the BDO,PS Bonth to the successful bidder otherwise the bid of the successful bidder shall be cancelled. Further proceeding for blacklisting shall be initiated against the bidder. If the APS is submitted in shape of Bank Guarantee by the bidder. then the validity of the Bank Guarantee should be for a minimum period equal to the period allowed for completion of the work plus defect liability period of one year and one month extra for transaction period.

- 8.** Submission of more than one tender paper by bidder for a single work will be liable for rejection of all such tender papers.
- 9.** Validity of tender shall be a period of 180 (One hundred eighty) days from the last date of receipt of bids. If any bidder/tenderer withdraw his bid or tender before the said period or make any modification in terms and conditions of the bid, the EMD deposited at the time of submission of the tender shall stands forfeited.
- 10.** The contractor has to quote the percentage excess or less upto two digits only after decimal point. If he quotes the percentage excess or less in more than two digits after decimal points the first two digits after decimal point shall only be considered without rounding off.
- 11.** In the eventually of failure on the part of lowest successful bidder to produce the original documents, he or she shall be debarred in future from participating in tender for 3 years and action will be initiated for blacklisting by the competent authority.
- 12.** **The Block Development Officer, Dhamnagar reserves the right to reject any or all the tenders without assigning any reason thereof .Other details can be seen in the bidding documents.**
- 13.** The bidder who will quote his/her rate more than 14.99% Less, he will be submit the written clarification including detailed price analyses of its bid price in relation to scope ,schedule, resource mobilization ,allocation of risks and responsibilities at the time of tender, otherwise their bid will be rejected.(As the work is emergency in nature the above requirments must be furnished).


Block Development Officer
Dhamnagar
Dhamnagar

Memo No- 3070 **Date- 30.06.2026**

Copy submitted to the Director, I & PR, Govt. of Odisha, Bhubaneswar for kind information.

D. 30.6.26
Block Development Officer
Block Development Officer
Dhamnagar

Memo No- 3071 **Date- 30.06.2026**

Copy Submitted to The Collector & DM, Bhadrak/CDO-cum-EO, ZP, Bhadrak/ DWO, Bhadrak/ District Planning Officer, Bhadrak/DI&P.R.O, Bhadrak for favour of kind information & necessary action.

D. 30.6.26
Block Development Officer
Block Development Officer
Dhamnagar

Memo No- 3072 **Date- 30.06.2026**

Copy forwarded to EE, Bhadrak/ EE, RWS & S. Bhadrak, EER & B Divison, Bhadrak/ EE,M.I. Divison, Bhadrak EER.W Divison, Bhadrak All BDOs of Bhadrak District/ Tahasildar, Dhamnagar/ IIC, Dhamnagar, Dhamnagar PS/ CDPO, ICDS, Dhamnagar for information & necessary action with request to display in their Notice board for wide circulation.

D. 30.6.26
Block Development Officer
Block Development Officer
Dhamnagar

Memo No- 3073 **Date- 30.06.2026**

Copy forwarded to The DeGM, Bhadrak for information with a request to upload the detail tender call notice, tender schedule and the bid documents in the official website of Bhadrak i.e <http://bhadrak.odisha.gov.in>

D. 30.6.26
Block Development Officer
Block Development Officer
Dhamnagar

Memo No- 3074 **Date- 30.06.2026**

Copy to Office Notice Board & C.P,Dhamnagar Block to assist for uploading the DTCN & bid documents at NIC, Bhadrak.

D. 30.6.26
Block Development Officer
Block Development Officer
Dhamnagar

Annexure-1

SI NO	BID IDENTIFICATION NUMBER	NAME OF THE WORK	APPROXI. EST COST PUT TO TENDER	CLASS OF CONTRACTOR	EMD(1%)Approx.	COST OF TENDER PAPER	TIME OF COMPLETION
1	2	3	4	5	6	7	8
1	PSD-01/2025-26	Construction of GPLF Building at Anandapur	Rs. 25,00,600/-	'B' & 'C'	Rs.25,006/-	Rs.6,000/-	SIX CALENDAR MONTH
2	PSD-02/2025-26	Construction of GPLF Building at Bamkura	Rs. 25,15,459/-	'B' & 'C'	Rs.25,160/-	Rs.6,000/-	SIX CALENDAR MONTH
3	PSD-03/2025-26	Construction of GPLF Building at Hasanabad	Rs. 24,99,436/-	'B' & 'C'	Rs.25,000/-	Rs.6,000/-	SIX CALENDAR MONTH
4	PSD-04/2025-26	Construction of GPLF Building at Nadigaon	Rs. 24,94,788/-	'B' & 'C'	Rs.25,000/-	Rs.6,000/-	SIX CALENDAR MONTH
5	PSD-05/2025-26	Construction of GPLF Building at Karada	Rs.24,99,436/-	'B' & 'C'	Rs.25,000/-	Rs.6,000/-	SIX CALENDAR MONTH
6	PSD-06/2025-26	Construction of GPLF Building at Khadipada	Rs. 24,97,970/-	'B' & 'C'	Rs.25,000/-	Rs.6,000/-	SIX CALENDAR MONTH
7	PSD-07/2025-26	Construction of Additional Class Room at Indragobinda Nodal High School, GP-Daipur	Rs.14,70,473	'C' & 'D'	Rs.14,705/-	Rs.6,000/-	SIX CALENDAR MONTH
8	PSD-08/2025-26	Construction of Additional Class Room at Khangara Nodal UPS, GP-Karada.	Rs.13,25,408/-	'C' & 'D'	Rs.13,255/-	Rs.6,000/-	SIX CALENDAR MONTH

9	PSD-09/2025-26	Construction of Additional Class Room at Dhamnagar Feeder Primary School, Dhamnagar NAC.	Rs.13,24,393/-	'C' & 'D'	Rs.13,257/-	Rs.6,000/-	SIX CALENDAR MONTH
10	PSD-10/2025-26	Construction of Additional Class Room at Sahaspur Nodal UPS GP-Sahaspur.	Rs.13,25,685/-	'C' & 'D'	Rs.13,257/-	Rs.6,000/-	SIX CALENDAR MONTH


 Block Development Officer
 Block Development Office
 Dhamnagar

GOVT. OF ODISHA
PANCHAYATI RAJ & DW DEPARTMENT



PANCHAYAT SAMITI
DHAMNAGAR

Name of the work

CONSTRUCTION OF ADDITIONAL CLASS
ROOM AT.SAHASPUR NODAL UPS ,G.P.
SAHASPUR, BLOCK. DHAMNAGAR, DIST.
BHADRAK.

Estimated Cost :

Rs. 18 ,33 ,000.00

(Rupees Eighteen Lakhs thirty three
Thousand) Only

Agency : Block Development Officer
,Dhamnagar
Year : 2025-26
Scheme : S & ME

REPORT :

Name of the work : CONSTRUCTION OF ADDITIONAL CLASS ROOM AT.SAHASPUR NODAL UPS ,G.P. SAHASPUR, BLOCK. DHAMNAGAR, DIST. BHADRAK.

Estimated Cost : Rs. **18 ,33 ,000.00**
(Rupees Eighteen Lakhs thirty three Thousand) Only

Year : 2025-26

Scheme S & ME

Sanction order No.- 6745/PR & DW dt. 06.03.2026

New Labour Rate Order:- No.- LESI-LL1-III-0081-2017-5308/LESI, Dt. 18/07/2024


In this estimate, necessary RCC frame structure has been adopted for the buildings using standard specifications, following provisions has been provided in this estimate. One Class Room of size 26'x17' and the proposed structure will be constructed in the premises of existing school. Accordingly, the provision of foundation in view of soil condition S.U.R pile has been provided in the estimate basing upon the design. The items of the work is mentioned below.

- 1 RCC frame structure with 300mm dia S.U.R 5mtr depth Pile foundation, pile cap as per drawing & earthwork in excavation for bed cutting below cap and built up area has been adopted
- 2 RCC M20 grade concrete for column as per drawing, grade beam, beam, lintel, slab as per IS 456 2000(For G.F)
- 3 Fly ash Bricks masonry work in C.M(1:6) for Foundation and Plinth
- 4 Fly ash Bricks in C.M(1:6) for superstructure
- 5 MS reinforcement of grade Fe415
- 6 12mm CP in cm (1:6) for outside , 16mm cp in cm(1:6) for inside and 6mm CP in cm(1:4) with close deep chipping for RCC work
- 7 Inside wall finished with 2 coat plastic paint over Acrylic wall putty, where as outside wall finished with weather coat paint.
- 8 G.I. grill finished with 2 coat enamel paint over 1 coat red oxide primer
- 9 Vitrified tile in floors of rooms and corridor. chequered tile for ramp
- 10 Provision for electrification

The analysis of rates for this estimate has been prepared with O/H charges & contractor's profit (7.5%+7.5%) each with 1% labourcess followed to S.R. 2022 post G.S.T. (18% G.S.T. included in the estimate) including work contingency @ 1% & current labour rate, as the work will be executed through open tender process. The standard specification will be maintained at the time of execution of work. Further detailed pre-measurement of project will be recorded before execution of work along with photocopy of project will be enclosed with case record.

The feasibility of the project has been verified by the concerned Asst. Engineer/Junior Engg , Asst. Executive Engineer. The project will be completed within the estimated cost in all respect. The detailed drawing has been enclosed with estimate.


Technical Consultant
Dhamnagar Block


Asst. Executive Engineer
Dhamnagar Block


Block Development Officer
Dhamnagar

**CONSTRUCTION OF ADDITIONAL CLASS ROOM AT SAHASPUR NODAL UPS ,G.P.
SAHASPUR, BLOCK. DHAMNAGAR, DIST. BHADRAK.**

SI .	DESCRIPTION			AMOUNT	
					(Rs.)
1	PART(A) - CIVIL COST			Rs.	13 ,25 ,685.00
2	Sub Total (A)			Rs.	13 ,25 ,685.00
3	Add CGST	9.00%		Rs.	1 ,19 ,312.00
4	Add SGST	9.00%		Rs.	1 ,19 ,312.00
5	Sub Total (B)			Rs.	15 ,64 ,309.00
6	Provision for electrification with conceal wiring	@	2.00%	Rs.	39,771.00
8	Provision for Furnitures		L.S.	Rs.	2,00,000.00
9	Provision for Blackboard of Size (12ft x 4ft)		L.S.	Rs.	6,000.00
10	Provision for Display Board		L.S.	Rs.	3,663.00
11	Provision for Fire fighting arrangement		L.S.	Rs.	6,000.00
12	Add Works Contingency	@	1%	Rs.	13,257.00
13	Grand Total (C)			Rs.	18 ,33 ,000.00

(Rupees Eighteen Lakhs thirty three Thousand) Only


Technical Consultant
Dhamnagar Block


Asst. Executive
Engineer


Block Development Officer
Dhamnagar

DETAIL ESTIMATE FOR

CONSTRUCTION OF ADDITIONAL CLASS ROOM AT.SAHASPUR NODAL UPS
G.P. SAHASPUR, BLOCK. DHAMNAGAR, DIST. BHADRAK.

NO.	DESCRIPTION	RATE	UNIT	AMOUNT.
1	300 mm dia 5.0 mtr. Lenth single under ream pile with R.C.C M-20 using 20 mm and down graded size black hard granite C.B. chips including cost of boring but excluding cost of M.S/Tor steel and labour charges for cutting,bending,binding of steel. No of pile 5.0mtr depth = 22	5,361.29	/each	117948.00
2	Earth work in hard soil within initial lead of 50m. And initial lift of 1.5m.including rough dressing and leveling the ground. Cap- 1 11 X 6.25 X 2.50 X 1.00 = 171.875 cft wall line 3 X 27.66 X 1.00 X 1.00 = 82.98 cft wall line 2 X 17.00 X 1.00 X 1.00 = 34.00 cft wall line 2 X 6.00 X 1.00 X 1.00 = 12.00 cft Step 1 X 27.66 X 4.16 X 1.00 = 115.07 cft Ramp wall 2 X 20.00 X 1.00 X 1.00 = 40.00 cft 455.92 cft Deduction Cap- 1 11 X 6.25 X 1.00 X 1.00 = 68.75 cft pile 22 X 0.785 X 1.00 X 1.00 = 17.27 cft 86.02 cft 455.9 - 86.02 = 369.90 cft Total = 369.90 cft 10.47 cum	276.89	/cum	2899.00
3	Sand filling in foundation and plinth well watered rammed etc. complete. Cap- 1 11 X 6.25 X 2.50 X 0.33 = 56.7 cft wall line 3 X 27.66 X 1.00 X 0.33 = 27.4 cft wall line 2 X 17.00 X 1.00 X 0.33 = 11.2 cft wall line 2 X 6.00 X 1.00 X 0.33 = 4.0 cft class Room 1 X 26.00 X 17.00 X 2.50 = 1105.0 cft ver 1 X 26.00 X 6.00 X 2.50 = 390.0 cft Step 1 X 27.66 X 4.16 X 0.50 = 57.5 cft Ramp wall 2 X 20.00 X 1.00 X 0.50 = 20.0 cft inside ramp 1 X 20.00 X 3.33 X 1.50 = 99.9 cft 1771.71 cft Deduction Cap- 1 11 X 6.25 X 1.00 X 0.33 = 22.69 cft pile 22 X 0.785 X 1.00 X 0.33 = 5.70 cft 28.39 cft 1771.71 - 28.39 = 1743.33 cft 49.37 Cum	1,124.51	/cum	55517.00
4	C.C. (1:3:6) using 4cm. Size H.G. metal(T & P) etc. complete Cap- 1 11 X 6.25 X 2.50 X 0.33 = 56.72 cft wall line 3 X 27.66 X 1.00 X 0.33 = 27.4 cft wall line 2 X 17.00 X 1.00 X 0.33 = 11.2 cft wall line 2 X 6.00 X 1.00 X 0.33 = 4.0 cft Room 1 X 26.00 X 17.00 X 0.33 = 145.9 cft ver 1 X 26.00 X 6.00 X 0.33 = 51.5 cft Step 1 X 27.66 X 4.16 X 0.33 = 38.0 cft Ramp wall 2 X 20.00 X 1.00 X 0.33 = 13.2 cft inside ramp 1 X 20.00 X 3.33 X 0.33 = 22.0 cft 369.77 cft Deduction Cap- 1 11 X 6.25 X 1.00 X 0.33 = 22.69 cft pile 22 X 0.785 X 1.00 X 0.33 = 5.70 cft 28.39 cft 369.8 - 28.39 = 341.39 cft 9.67 Cum	6,813.75	/cum	65889.00
5	1" thick D.P.C with C.C(1:2:4) using 12mm. Chips etc. cpmplete as per direction of Engg-in-Charge . wall line 3 X 27.66 X 0.83 = 68.9 cft wall line 3 X 17.00 X 0.83 = 42.3 cft wall line 3 X 6.00 X 0.83 = 14.9 cft Total = 126.14 cft 3.57 Cum	381.73	/cum	1363.00
6	R.C.C.work in M20 grade using 20mm & down graded chips etc.complete. etc. complete. (A) Cap- 1 11 X 5.75 X 2.00 X 1.66 = 209.99 cft Total or 209.99 cft 5.95 cmt	7,284.36	/cum	43342.00

9 Fly ash Brick masonry in C.M. (1:6) for superstructure including cost, conveyance, royalties, plumbing, curing and all labour charges etc. complete

Wall line	2 X	27.66 X	0.83 X	9.00 =	413.24 cft
Wall line	2 X	17.00 X	0.83 X	9.00 =	253.98 cft
head rn	1 X	27.66 X	0.83 X	2.16 =	49.59 cft
head rn	2 X	6.00 X	0.83 X	2.16 =	21.51 cft
					738.32 cft

Deduction

Column	6 X	0.83 X	0.83 X	9.00 =	37.20 cft
Column	3 X	0.83 X	0.83 X	2.16 =	4.46 cft
D	2 X	4.0 X	0.83 X	7.0 =	46.5 cft
W	2 X	4.0 X	0.83 X	4.5 =	29.9 cft
skylight	4 X	2.0 X	0.83 X	1.0 =	6.6 cft

Total =			738.32 -	124.66 =	613.66 cft
---------	--	--	----------	----------	------------

or 17.38 cum 6.847.33 /cum 105103.00

10 8mm Thick cement plaster in C.M (1:4) for Ceiling including cost, conveyance, royalties, and watering, curing and all labour charges etc complete

Room	1 X	28.0 X	17.0	=	442 sft
Verandah	1 X	26.00 X	6.000	=	156 sft
beam	1 X	17.00 X	2.000	=	34 sft
column	3 X	3.33 X	7.000	=	69.93 sft
Chajja	2 X	5.00 X	3.25	=	32.5 sft
Front chajja	1 X	30.66 X	3.25	=	99.645 sft
Front chajja	2 X	6.00 X	3.25	=	39 sft
Karnish	1 X	2 X	28.66 +	26.50)=	110.3 sft
			110.32 x	0.83 =	91.6 sft

Total 964.64 sft

or 89.650 sqm 215.04 /sqm 19278.00

11 12mm Thick cement plaster in C.M (1:6) over superstructure for bothside wall including cost, conveyance, royalties, and watering, curing and all labour charges etc complete.

out side		2 X	27.66 X	13.00 =	719.2 sft
out side		2 X	18.66 X	13.00 =	485.2 sft
verandah		1 X	26.33 X	3.00 =	79.0 sft
verandah		2 X	6.00 X	3.00 =	36.0 sft
step		5 X	27.66 X	0.83 =	114.8 sft
step		6 X	27.66 X	0.50 =	83.0 sft
Ramp wall		2 X	20.00 X	1.66 =	66.4 sft
					1583.5 sft

Deduction

D	2 X	4.00 X	7.0	0.5 =	28.0 sft
W	2 X	4.00 X	4.5 X	0.5 =	18.0 sft
					46.0 sft

Total =			1583.48 -	46.00 =	1537.48 sft
---------	--	--	-----------	---------	-------------

OR 142.9 sqm 195.33 /sqm 27910.00

12 16mm Thick cement plaster in C.M (1:6) over superstructure for bothside wall including cost, conveyance, royalties, and watering, curing and all labour charges etc complete.

in side		2 X	26.00 X	10.00 =	520.0 sft
in side		2 X	17.00 X	10.00 =	340.0 sft
verandah		1 X	26.33 X	3.00 =	79.0 sft
verandah		2 X	6.00 X	3.00 =	36.0 sft
					975.0 sft

Deduction

D	2 X	4.00 X	7.0 X	0.5 =	28.0 sft
W	2 X	4.00 X	4.5 X	0.5 =	18.0 sft
					46.0 sft

Total =			974.99 -	46.00 =	929.0 sft
---------	--	--	----------	---------	-----------

OR 86.337 sqm 280.72 /sqm 24237.00

13 Fixing Vitrified tiles in floors of size 600mm x600 mm of approved make conforming class Room

class Room	1 X	26.00 X	17.00	=	442 sft
Verandah	1 X	26.00 X	6.00	=	156 sft
					598 sft

=	0.0 sft			or	55.576 sft
---	---------	--	--	----	------------

1143.65 /sft 63560.00

14 Fixing Vitrified tiles in dados skirting and risers of stepson 12 mm thick cement plaster(1:3)

class Room	2 X	26.00 X	0.50	=	26 sft
class Room	2 X	17.00 X	0.50	=	17 sft
Verandah	1 X	27.66 X	0.50	=	14 sft
column	3 X	3.33 X	0.50	=	5 sft
					62 sft

Deduction

D	2 X	4.00 X	0.5 X	1 =	4.0 sft
					57.8

				or	5.37 smt	1301.32 /smt	6993.00
15	Fixing Chequered tiles in floors,treads or steps and landings on 25 mm thick CM (1:1) jointed jointed with neat cement slurry mixed with pigments to match the shades includind cost for rubbing, polishing & cost of marbel tiles etc. complete as per direction of Engg-in-Charge . ramp	1 X	20.00 X	5.00	=	100.00 sft 100.00 sft	
				or	9.294 smt	979.23 /smt	9101.00
16	Painting one coat any approved primer with wall cement primer water bound with cost and labour etc complete		142.9	86.3	89.65	318.88 smt	82.58 /sqm
17	Finishing with water based wall putty of approved make and finished smooth surfacecost of colour and all labour charges etc. complete.					175.99 smt	91.09 /sqm
18	Wall painting with plastic emulsion paint of approved shade etc complete cost of colour and all labour charges etc. complete.					175.99 smt	108.92 /sqm
19	Wall painting two coats with weather coat for outside wall cost of colour and all labour charges etc. complete.					142.89 smt	98.51 /sqm
20	20mm Thick cement plaster in C.M (1:4) for grading plaster					732.99 sft	
				or	68.122 smt	304.58 /sqm	20748.00
21	Fitting & fixing of door & windows in G.I. sheet as per drawing at all heights including cost of G.I.sheet and all labour charges etc. complete.						
	Door	2 X	4.00 X	7.0	=	56.0 sft	
	Window	2 X	4.00 X	4.5	=	36.0 sft 92.0 sft	
	Required grill		3.5	kg/	sft	=	322.0 Kgs
22	Fitting & fixing of door & windows in G.I. sheet as per drawing at all heights including cost of G.I.sheet and all labour charges etc. complete.						
	Window grill	2 X	4.00 X	4.5	=	36.0 sft 36.0 sft	
	Required grill		2.5	kg/	sft	=	90.0 Kgs
23	Two coats of painting with well paint over Door & Window.						
	Both side	184.0	36.0	220.0	or	20.446 smt	264.80 /sqm
24	Supplying,fitting & fixing of stainless steel of 304 grade in Hand Railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm.x2mm. @ 0.90m. C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification,buffing,polishing etc. with cost, conveyance, taxes of all materials labour T & D etc. provided for the completion in all					9.00 m	3595.93 rmt
							32363.00
						Total	= 1325685.00
23	Work contigency		1%				13257.00
23	GST		18%				238624.00
24	FURNITURE						200000.00
24	provision for electrification						39771.00
24	provision for Black board of size 12x4 ft size						6000.00
24	provision for Fire fighting arrangement						6000.00
24	provision for Display board, Photocopy						3663.00
						G.total	1833000.00
						Limited to	18,33,000.00
						(Rupees Eighteen lakhs thirty three thousand) only	

Administratively approved for
Rs. 1833000.00
(Rupees Eighteen lakhs thirty three thousand) only

B.D.O.
Dhamnagar

Technically approved for
Rs. 1833000.00
(Rupees Eighteen lakhs thirty three thousand) only

Asst. Executive Engineer
Dhamnagar

Technical Consultant
Dhamnagar